February 2008



# Brown Lake Hydrologic Restoration (CS-09)

De-authorized

Cost figures as of: July 2025

### **Project Status**

**Approved Date:** 1993 **Project Area:** 916 acres **Approved Funds:** \$1 M **Total Est. Cost:** \$1 M

Net Benefit After 20 Years: 37 acres

**Status:** De-authorized

Project Type: Hydrologic Restoration

**PPL#:** 2

#### Location

This project is located in Cameron and Calcasieu parishes, approximately 3 miles north of Hackberry, Louisiana.

## **Problems**

Saltwater intrusion from the Calcasieu Ship Channel and increased tidal amplitudes have caused 90 % of the marsh in this system to be lost.

# Restoration Strategy

This project will restore, to the extent possible, the altered hydrology of approximately 2,800 acres of wetlands in the area of Brown Lake. This project consists of the installation of two water control structures, two freshwater introduction structures, the rehabilitation or construction of approximately 30,000 linear feet of boundary levees, and 20,500 linear feet of terraces and associated vegetative plantings.

# **Progress to Date**

This project is being coordinated with the U.S. Army Corps of Engineers dredging program. Several pipeline-related issues have caused delays, but these issues have been resolved. The permits, the effects of Crab Gully, and the operations agreements have been addressed. Contract advertisement will take place after receiving Phase 2 funding approval from the Louisiana Coastal Wetlands Conservation and Restoration Task Force.

This project is on Priority Project List 2.



In order to prevent wind generated wave erosion from destroying the freshly added spoil, vegetation is planted to get a head start on providing cover for the fragile soil.

For more information, please contact:



#### **Federal Sponsor:** Natural Resources Conservation Service Alexandria, LA (318) 473-7756



**Local Sponsor:**Coastal Protection and Restoration Authority
Baton Rouge, LA
(225) 342-4736

