## Little Lake Shoreline Protection/Dedicated Dredging near Round Lake

Candidate Project
for the
Eleventh Priority List
of the
Coastal Wetlands Planning, Protection and Restoration Act



Proposed by

National Marine Fisheries Service

and

Louisiana Department of Natural Resources

#### **Wetland Value Assessment**

Contact: Rachel Sweeney (NMFS) -- 225/389-0508

**Draft:** September 26, 2001 **Revised:** — October, 2001

#### Project Information Sheet Format for Wetland Value Assessment

**Project Name:** Little Lake Shoreline Protection/Dedicated Dredging near Round Lake

**Sponsoring Agency:** National Marine Fisheries Service

EnvWG contact - Rachel Sweeney 225/389-0508 EngWG contact - Rachel Sweeney 225/389-0508

Project Area: 1374 acres

Area A: 1074 acres

Area B: 94 acres (boundary determined by anticipated extent of area to be lost due to

shoreline erosion)

Area C: 206 acres (boundary determined by anticipated extent of area to be lost due

to shoreline erosion)

#### **Problem:**

Shoreline erosion and wetland loss in the Little Lake mapping unit resulted in the loss of approximately 53% of the 1932 acreage by 1990. The high wetland loss rate in this area is generally caused by shoreline erosion, subsidence, and channel construction which results in altered hydrology. It is projected that an additional 14,000 acres will be lost in this mapping unit by 2050 (Coast 2050, Appendix D).

#### Goals:

Marsh Creation: Create 488 acres of intertidal elevation suitable for the establishment

of vegetated wetlands at TY1

Create 143 acres of vegetated emergent marsh at TY3 Create 466 acres of vegetated, emergent marsh at TY5

Reduce FWOP loss rate of 1.785%/yr by 50%

Marsh Nourishment: Maintain 508 acres of marsh at TY5

Maintain 444 acres of marsh at TY20

Reduce FWOP loss rate of 1.785%/yr by 50%

Prevent shoreline erosion

#### **Project Features:**

#### **Shoreline Protection**

Installation of 20,620 feet of shoreline protection (geotextile encapsulated lightweight aggregate core capped with rock) in open water, generally along the -2 contour, with a crest elevation approximately 2 feet above mean water. The shoreline protection will include offset gaps with a 10-foot base width every 1,000 feet to provide adequate drainage and marine organism access. Material

generated by access/floatation dredging ( $\pm$  404,000 cy) may be used beneficially; however, no credit is included in this WVA for such acreage.

#### Marsh Creation and Nourishment

In Area A, material will be dredged from Little Lake to create and nourish marsh. For marsh creation, dredged material will be placed to intertidal elevations in approximately 90% of the 2001 open water acres to create approximately 488 acres of intertidal elevation. Approximately 10% of the existing interior open water will not be filled to maintain selected features such as tidal creeks and ponds. Additionally, six-12 inches of dredged material will be placed over 532 acres of existing marsh for marsh nourishment. Retention dikes will be constructed as required to provide containment along the perimeter of the project area where existing marsh, spoil banks, etc., will not adequately contain the material. Internal low-level training dikes may also be used to direct the flow of dredged material. All dikes will be gapped prior to demobilization by the dredging contractor. Due to the large size of the marsh creation area, only limited vegetative plantings (± 50 acres) will be used in areas determined to lack vegetative source material. No credit is incorporated into the WVA for these plantings.

#### **Monitoring Information:**

**Shoreline Protection** 

- Freshwater Bayou (ME-04) was completed in 1995. Erosion occurred at all six reference area sites, averaging 6.54 ft/yr over a 14.5 month period. Along the project area shoreline, progradation of the vegetated edge occurred at 15 of the 27 sites, erosion occurred at 8 sites, and no change was observed at 4 sites. Overall the shoreline prograded at an average rate of 2.34 ft/yr.
- Cameron Prairie Refuge (ME-09) shoreline data indicates the spoil bank erosion rate was -3.76 ft/yr between March 1995 and May 1997 in the reference area which is located directly east of the project area. The shoreline in the project area prograded at a rate of \_4.61 ft/yr. Change in shoreline position in the project area ranged from +23 ft to +2 ft. as compared to reference area shoreline change from -19 ft. to -3 ft.
- Boston Canal (TV-09) rock breakwaters have completely halted shoreline erosion behind the structures and have accumulated sediments. Analysis of 11 elevation profile from 1994 overlaid with the 1995 profiles indicate that approximately 1.5 to 4.5 ft of sediment were deposited between the breakwater and the existing shoreline. Greater gains were documented adjacent to the bayward breakwaters.
- To date, *Turtle Cove (PO-10)* has achieved protecting the shoreline and appears to have promoted deposition behind the gabion. The shoreline has prograded +3.36 ft/yr behind the gabion, and sediment elevation increased 0.26 ft/yr. Land area increased 5.78 ac.
- Fresh water Bayou Bank Protect (T/V-11)- no specific conclusion on breakwater performance can be made at this time due to the absence of post construction data. Partial structure failure has resulted making maintenance necessary.
- Bayou Segnette Wetlands (BA-16)- no statically based conclusions on project effects on shoreline erosion. Reported many severely eroded portions existed where the rock berm was bordered only by open water.

- Baie De Chactas (BA-05c)- averaged -7 ft/yr pre-project between 1951 to 1990 (north shore Lake Salvador). Post construction of an oyster shell berm indicated subsequent breaching and reinitiation of shoreline recession. In 1995, the presence of the shell berm could no longer be detected. Salinity measurements averaged 0.2 ppt.
- Lake Salvador Phase II (BA-15) creation of emergent elevations behind the continuous rock breakwater were successful based on as-built inspection immediately post construction and annually since construction. The created elevations were colonized soon after placement (during construction), with lesser vegetation present where large quantities of shell were present in the dredged sediment. Target elevations were too high and not strictly enough enforced during construction resulting in the creation of some uplands and shrub/scrub wetlands.

#### Marsh Creation

- 1 year post-construction
  - Queen Bess (BA-05b)- showed 28% coverage after 8 months post construction with some plantings conducted.
  - O BBWW (BA-19) showed 0% cover
  - Atchafalaya Sediment Delivery showed 49% cover
  - Lake Chapeau showed 0% cover
- 2 years post-construction
  - O BBWW (BA-19) showed 0% cover
- 3 years *Bayou LaBranche (P0-17)* 51% emergent marsh (82% land)
- Hydroperiod data at LaBranche showed greater flooding duration inside vs the reference area likely due to the containment dikes and unauthorized maintenance of closures were breaches had formed.

#### Historical and present vegetative community

Project area marshes have been historically classified as both intermediate (1949) and fresh (1956). Between the 1950's and 1970's, project area marshes had shifted to higher salinity communities, and were classified as intermediate to brackish. More recent habitat analyses classify Area A as intermediate, and Areas B and C as brackish. We do note that at each year of habitat classification, project area marshes are on or near the line of demarcation between habitat types. Observations from the July 12, 2001 interagency site visit suggest that all three areas are similarly dominated by *Spartina patens* with consistent, but less dominant occurrences of *Distichlis spicata* and *Juncus roemerianus*. Based on field observation it appears that Areas A, B, and C are essentially the same habitat types.

Based on historical salinity data, and anticipated effects of the Davis Pond Freshawater Diversion porject, the intermediate model will be used to conduct the WVA.

### Soil types in the project area

Project area soils are Lafitte-Clovelly.

#### Land loss data

### <u>Marsh acreage and land loss rates - Area A</u> Marsh Acreage

The data and analyses provided by the COE and USGS regarding marsh acreage and land loss rates reveals several inconsistencies. The pertinent results of the COE and USGS analyses are summarized in Tables 1 and 2. (Note that the "marsh acreage" data in Table 1 has been transformed into "% marsh" to ease comparison between the two data sources because the COE's analysis was performed for a 1040 acre project area while USGS's analysis was conducted for a project area of 1,073 acres; the raw data and analyses are attached in Appendix A).

<u>Table 1</u> – Comparison of COE and USGS estimates of "marsh acreage." Note that information has been transformed into percent marsh to ease comparison due to slightly different project boundaries used in each analysis. Original data

included in Appendix A.

| meradea m 7 q        | P    |          |      |      |      |      |               |      |      |
|----------------------|------|----------|------|------|------|------|---------------|------|------|
|                      |      | "1950's" | 1956 | 1974 | 1978 | 1983 | 1988/<br>1990 | 1990 | 1993 |
| % of area classified | COE  | 99%      |      | 90%  |      | 90%  |               | 87%  |      |
| as marsh or land     | USGS |          | 97%  |      | 86%  |      | 48%           |      | 60%  |

Regarding marsh acreage in Area A, both COE and USGS data summarized in Table 1 indicate consistent estimates for marsh acreage from the 1950s to mid 1970s. However, major discrepancies are evident in comparing the two data sets for the 1980s and 1990s, with Corps data consistently indicating much higher marsh acreage than those estimated by the USGS analyses. Inspection of both 1995 aerial infrared photographs and the 1998 DOQQs indicates that Area A contains significantly less marsh than the COE's 1990 estimate of 87% marsh. In order to determine the relative accuracy of the 1988/90 and 1993 estimates provided by USGS, the GIS images for the 1988/90 habitat classification and 1993 land/water analysis were copied onto transparencies, and overlaid on the 1995 photography as well as the 1998 DOQOs. Both the 1988/90 habitat analysis and the 1993 land/water analysis appear relatively consistent with the 1995 and 1998 images of Area A. Inspection of the 88/90 analysis does indicate that some areas classified as open water in 1988/90 remain as marsh on the 1995 and 1998 images. Experience in interpreting the 1988/90 imagery and resultant analyses have led to a common understanding that in many cases, the 1988 imagery produces an artificially high estimate of water areas and consequently, a skewed estimate of marsh acres. Comparison of the 1993 land/water analysis to the 1995 and 1998 images shows a good correlation. Noting that various marsh classes are the only "land" classes in Area A (except for .07% of the area which was classified as Shrub/Scrub), we propose to use the "land" acreage value of 644 acres from USGS's 1993 land to water analyses as the basis for determining the 2001 acreage of marsh in Area A.

#### Land Loss Rates

The discrepancies between the COE and USGS data sets also result in significant differences in the land loss rates for Area A. Land loss rates calculated from the two data sets are summarized below in Table 2

Table 2 – Comparison of land loss rates calculated from COE and USGS data

| Period | 1930's - 1950's | 1950's - 1974 | 1956 - 1978 | 1974 - 1983 | 1978 - 1988/90 | 1983 - 1990 | 1978 - 1993 |
|--------|-----------------|---------------|-------------|-------------|----------------|-------------|-------------|
| COE    | 0%/yr           | 0.38%/yr      |             | 0.01%/yr    |                | 0.28%/yr    |             |
| USGS   |                 |               | 0.58%/yr    |             | 3.86%/yr       |             | 2.01%/yr    |

Based on our comparison of the 1978 analysis against the 1974 aerial photographs which indicate an excellent agreement between images and our analyses of the relative accuracy of the 1993 land to water analysis, we propose to use a land loss rate of 2.01%/yr (as derived from the 1978 and 1993 data) for Area A. This rate was determined based on two years which we believe the data sources and resultant analyses are most accurate. As a comparison, the estimated land loss rates for the Little Lake mapping unit, derived from the Coast 2050, Appendix D, are summarized in Table 3. Although the proposed loss rate of 2.01%/year is slightly higher than the overall rates for the entire Little Lake mapping unit, the land loss maps clearly indicate that some of the loss in this mapping unit in concentrated in the vicinity of the project area.

Table 3 - Land loss rates calculated for the Little Lake Mapping Unit; derived from Coast 2050, Appendix D.

| Period    | 1932-1956   | 1956 - 1974 | 1974 - 1983 | 1983 - 1990 |
|-----------|-------------|-------------|-------------|-------------|
| Loss Rate | 0.39 %/year | 1.29 %/year | 1.78 %/year | 1.85 %/year |

#### **Shoreline Erosion**

Shoreline erosion rates were calculated by Del Bristch for Areas A, B, and C, independently. The positions of the 1932 and 1988 shorelines were measured at 21 transects, and annual rates were derived for each transect. Note that areas of extremely high localized erosion were not included in the analysis, and that the high and low values were not used when calculating the "average" rate (see Appendix B for Del's analysis and resulting erosion rates). We proposed to use the following shoreline erosion rates:

Area A: 20'/yr

Area B: 40'/yr Area C: 40'/yr

#### **AREA A**

#### V1 - Emergent Marsh

Assumptions: - 1993 USGS land acreage (644 acres) brought forward to 2001 by 1) applying 20'/year shoreline erosion over the 7541 feet of shoreline and prorating resulting acreage (3.46 acres) by 60% to adjust for land to water ratio (2.07 acres marsh lost annually due to erosion) and 2) applying land loss rate of 2.01%/year to the remaining acreage. (Appendix C).

TY0

2001 emergent marsh: 532 ac (50%) 2001 open water: 542 ac (50%)

2001 total: 1074 ac

#### **FWOP**

Assumptions: - Continued shoreline erosion of 20'/yr.

- Increased FWOP 2.01%/yr loss rate by 10% due to increasing fragmentation of existing marsh and continued deterioration of the shoreline. Decreased FWOP loss rate by 15% and 5% for the effects of Davis Pond and Bayou L'Ours Ridge, respectively. Resulting FWOP loss rate: 2.01%/yr \* 1.1% \* 0.85% \* 0.95% =

1.785%/yr (Appendix D).

TY1 emergent marsh: 521 acres (49%)

open water: 553 acres (52%)
TY20 emergent marsh: 336 acres (31%)

open water: 737 (69%)

-

#### **FWP**

Table 4 – Summary of V1 assumptions and calculations used in FWP scenario (full calculations in Appendix E)

| Project Area                         | 1074  | FWOP Loss Rate 1.785                         |  |  |  |  |  |  |
|--------------------------------------|-------|--|--|--|--|--|--|--|
| TY0 Marsh Acres: 532                 |       | Created Acres (90% of TY0 water acres): 488  |  |  |  |  |  |  |
| TY0 Water Acres: 542                 |       | Nourished Acres (100% TY0 marsh acres): 532  |  |  |  |  |  |  |
| FWP Land Loss Rates (%/yr)           |       |  |  |  |  |  |  |  |
| Created acres: 50% reduction in FWOP | 0.895 | Nourished acres: 50% reduction in 0.895 FWOP |  |  |  |  |  |  |

| TY1 acres         |  |     |  |  |  |  |  |
|-------------------|--|-----|--|--|--|--|--|
| Marsh Creation    | 10% of the created marsh credited at TY 1                  | 49  |  |  |  |  |  |
| Marsh Nourishment | 100% existing marsh nourished, 50% credit at TY1           | 266 |  |  |  |  |  |
| Total Marsh       |  | 315 |  |  |  |  |  |
| Project Area      | Project area= 1074-((75% of 488 acres)+(50% of 532 acres)) | 369 |  |  |  |  |  |

| TY3 acres         |  |     |  |  |  |  |  |
|-------------------|--|-----|--|--|--|--|--|
| Marsh Creation    | 30% created acreage - 3 yrs loss at .895%/year       | 143 |  |  |  |  |  |
| Marsh Nourishment | 100% nourished acres less 3 years loss at 1.34%/year | 518 |  |  |  |  |  |
| Total Marsh       |  | 661 |  |  |  |  |  |
| Project Area      | Project area= 1074-(70% of 488 acres)                | 732 |  |  |  |  |  |

| TY5 acres         |  |     |  |  |  |  |  |
|-------------------|--|-----|--|--|--|--|--|
| Marsh Creation    | 100% created acreage - 5 yrs loss at .895%/year      | 466 |  |  |  |  |  |
| Marsh Nourishment | 100% nourished acres less 3 years loss at 1.34%/year | 508 |  |  |  |  |  |
| Total Marsh       |  | 974 |  |  |  |  |  |

#### TY1

Assumptions: - Shoreline erosion is prevented.

- 90% of the existing open water area is filled to marsh elevation. Without the installation of vegetative plantings, 10% of the created acreage is credited at TY1.
- 100% of the existing marsh acreage is nourished with 6 12 inches of dredged material. 50% of the nourished acreage is credited at TY1.

### emergent marsh: 315 acres (85%)

Creation: [(0.9\*542 acres)\*.10 for credit in TY1 = 49 acres] and

Nourishment: [532 acres \* .5 for credit in TY1= 266 acres]

open water: 54 acres (15%)

#### TY3

Assumptions: - 30% credit for created acreage

- 100% credit for nourished marsh acreage.
- FWOP loss rate reduced by 50% for all created and nourished acreage (to 0.89%/yr). Three years of loss instantaneously applied to both created and nourished acres

#### emergent marsh: 661acres (90%)

Creation: [488 acres \*0.3 for credit in TY3 - (3 yrs \*(542\*0.895%/yr)) = 133

acres] and

Nourishment: [532 acres - 3\*(532\*0.895%/yr) = 518 acres]

open water: 71 acres (10%)

#### TY5

Assumptions: 100% credit for all created and nourished marsh acreage. Five years of loss instantaneously applied to both created and nourished acres.

### emergent marsh: 974 acres (91%)

Creation: [488 acres - (5 yrs\*(542\*0.895%/yr)) = 466 acres] and

Nourishment: [532 acres - 5\*(532\*0.895%/yr) = 508 acres]

open water: 100 acres (9%)

```
TY20 emergent marsh: 851 acres (79%)
```

open water: 223 acres (21%)

### **V2 - Submerged Aquatic Vegetation**

**FWOP** 

TY1 - TY20: 10%

**FWP** 

TY1 10%

TY3 15%

TY5 15%

TY20 15%

### V3 - Interspersion

#### **FWOP**

**TY0** 20% Class 1; 40% Class 3 and 40% Class 4

**TY1** 20% Class 1; 40% Class 3 and 40% Class 4

**TY20** 20% Class 2 and 80% Class 4

#### **FWP**

**TY1** 100% Class 1

**TY3** 100% Class 1

**TY5** 100% Class 1

**TY20** 70% Class 1 and 30% Class 2

#### V4 - Shallow Open Water Habitat

**FWOP** 

Survey data collected August 2001 indicates that the majority of the open water in the project area is less than 2.5 feet deep, and that approximately 55% is less than 1.5 feet at average water stages. It is assumed that FWOP, the ratio of deep to shallow open water will not change significantly, although the total amount of open water will increase.

**TY0** 55%

**TY1** 55%

**TY20** 55%

<u>FWP</u> The majority of shallow open water will be filled for marsh creation.

**TY1** 90%

**TY3** 90%

**TY5** 85%

TY20 80%

#### V5 - Salinity

<u>FWOP</u> and <u>FWP</u>; all TYs: 4 ppt

#### V6 - Fish Access

#### FWOP and FWP; all TYs: 1

#### AREA B

#### V1 - Emergent Marsh

Assumptions: -Assume 40'/year shoreline erosion over the 4,100 feet of shoreline for 20 years; 78% land to water ratio; and 200-foot offset for shoreline protection. Note, no land loss rate applied for FWP or FWOP scenarios.

(40"/yr)\*(20 yrs)\*(4,100 feet)=75 acres (75 acres)\*(0.78 land:water) =59 acres marsh and 16 acres water (200' offset)\*(4,100 feet) - 19 acres water

#### TY0

**2001** emergent marsh: **59** acres (**63%**)

**2001 open water: 35 acres (37%)** [16 acres + 19 acres]

**2001 total: 94 acres** 

#### **FWOP**

Assumption: Continued shoreline erosion of 40'/yr. Annual loss = (40')\*(4,100')\*(.78) = 3 acres

TY1 emergent marsh: 56 acres (60%) [59 acres - 3 acres] open water: 38 acres (40%)

**TY20** emergent marsh: 0 acre (0%) [56 acres-(19 yrs\*3 acres/yr)] open water: 94 acres (100%)

#### **FWP**

Assumption: Shoreline erosion is prevented TY1 emergent marsh: 59 acres (63%) open water: 35 acres (37%)

TY20 emergent marsh: 59 acres (63%) open water: 35 acres (37%)

#### **V2 - Submerged Aquatic Vegetation**

FWOP and FWP; all TYs: 0%

#### **V3** - Interspersion

#### **FWOP**

TY0 80% Class 2, 20% Class 4

TY1 80% Class 2, 20% Class 4

TY20 100% Class 5

#### **FWP**

TY1 80% Class 2, 20% Class 4

#### TY20 80% Class 2; 20% Class 4

#### V4 - Shallow Open Water Habitat

**FWOP** 

TY0 50%

TY1 50%

TY20 0%

**FWP** 

TY1 50%

TY20 50%

V5 - Salinity

<u>FWOP</u> and <u>FWP</u>; all TYs: 4 ppt

V6 - Fish Access

FWOP and FWP; all TYs: 1

#### **AREA C**

### V1 - Emergent Marsh

Assumptions: Assume 40'/year shoreline erosion over the 8,978 feet of shoreline for 20 years; 84% land to water ratio; and 200-foot offset for shoreline protection. Note, no

land loss rate applied for FWP or FWOP scenarios.

(40'/yr)\*(20 yrs)\*(8,978 feet)=165 acres

(165 acres)\*(0.84 land:water) =139 acres marsh and 26 acres water

(200' offset)\*(8,978 feet) = 41 acres water

TY0

**2001** emergent marsh: 139 acres (68%)

**2001 open water: 67 acres (32%)** [26 acres+41 acres]

2001 total: 206 acres

**FWOP** 

Assumption: Continued shoreline erosion of 40'/yr. Annual loss (40')\*(8,978')\*(.85) = 7 acres

TY1 emergent marsh: 132 acres (64%) [139 acres - 7 acres/yr]

open water: 74 acres (36%)

**TY20** emergent marsh: 0 acre (0%) [132 acres- (19 yrs\*7 acres/yr)]

open water: 206 acres (100%)

**FWP** 

Assumption: Shoreline erosion is prevented TY1 emergent marsh: 139 acres (68%)

open water: 67 acres (32%)

TY20 emergent marsh: 139 acres (68%)

open water: 67 acres (32%)

## V2 - Submerged Aquatic Vegetation

FWOP and FWP; all TYs: 0%

#### V3 - Interspersion

#### **FWOP**

TY0 75% Class 1 and 25% Class 4

TY1 70% Class 1 and 30% Class 4

TY20 100% Class 5

#### **FWP**

TY1 75% Class 1 and 25% Class 4

TY20 75% Class 1 and 25% Class 4

#### V4 - Shallow Open Water Habitat

#### **FWOP**

TY0 5%

TY1 4%

TY20 0%

#### **FWP**

TY1 5%

TY20 5%

#### **V5 - Salinity**

FWOP and FWP; all TYs: 4 ppt

#### V6 - Fish Access

FWOP and FWP; all TYs: 1

Project: Little Lake Shoreline Protection/Dedicated Dredging near Project Ar

Round Lake - Area A

Project Area: Fresh.....

0

0

0

0

0

0

0

0

0

0

Condition: Future Without Project Intermediate. 1,074

|          | ] [  | TY 0                |      | TY 1                |      | TY 20                |      |                      |      |                      |
|----------|--|---------------------|------|---------------------|------|----------------------|------|----------------------|------|----------------------|
| Variable |  | Value               | SI   | Value               | SI   | Value                | SI   |                      |      |                      |
| V1       | % Emergent   | 50                  | 0.55 | 49                  | 0.54 | 31                   | 0.38 |                      |      |                      |
| V2       | % Aquatic  | 10                  | 0.19 | 10                  | 0.19 | 10                   | 0.19 |                      |      |                      |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | %<br>20<br>40<br>40 | 0.44 | %<br>20<br>40<br>40 | 0.44 | <b>%</b><br>20<br>80 | 0.28 | 1<br>0<br>0.4<br>0.2 |      | 0<br>0.6<br>0<br>0.2 |
| V4       | %OW <= 1.5ft   | 55                  | 0.72 | 55                  | 0.72 | 55                   | 0.72 |                      |      |                      |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              | 4                   | 1.00 | 4                   | 1.00 | 4                    | 1.00 | 1.00                 | 1.00 | 1.00                 |
| V6       | Access Value fresh intermediate                                      | 1.00                | 1.00 | 1.00                | 1.00 | 1.00                 | 1.00 | 1.00                 | 1.00 | 1.00                 |
|          | Emergent Mars  |                     | 0.63 | EM HSI =            | 0.63 | EM HSI =             | 0.49 |                      |      |                      |
|          | Open Water H   | SI =                | 0.38 | OW HSI =            | 0.38 | OW HSI =             | 0.37 |                      |      |                      |

Project: Little Lake Shoreline Protection/Dedicated Dredging near FWOP

| FWUP     | <b>-</b>   |          |    |          |          |          |    |
|----------|--|----------|----|----------|----------|----------|----|
|          |  |          |    |          |          |          |    |
| Variable |  | Value    | SI | Value    | SI       | Value    | SI |
| V1       | % Emergent   |          |    |          |          |          |    |
| V2       | % Aquatic  |          |    |          |          |          |    |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | %        |    | %        |          | %        |    |
| V4       | %OW <= 1.5ft   |          |    |          |          |          |    |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              |          |    |          |          |          |    |
| V6       | Access Value fresh intermediate                                      |          |    |          |          |          |    |
|          | -  | EM HSI = |    | EM HSI = |          | EM HSI = |    |
|          |  | OW HSI = |    | OW HSI = | OW HSI = |          |    |

Project: FWOP Little Lake Shoreline Protection/Dedicated Dredging near

| -WOP     | =  |          |    |          |    |          |    | <del></del>      |                  |
|----------|--|----------|----|----------|----|----------|----|------------------|------------------|
| Variable |  | Value    | SI | Value    | SI | Value    | SI |                  |                  |
| V1       | % Emergent   |          |    |          |    |          |    |                  |                  |
| V2       | % Aquatic  |          |    |          |    |          |    |                  |                  |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | %        |    | %        |    | %        |    | 0<br>0<br>0<br>0 | 0<br>0<br>0<br>0 |
| V4       | %OW <= 1.5ft   |          |    |          |    |          |    |                  |                  |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              |          |    |          |    |          |    |                  |                  |
| V6       | Access Value fresh intermediate                                      |          |    |          |    |          |    |                  |                  |
|          |  | EM HSI = | •  | EM HSI = |    | EM HSI = | •  |                  |                  |
|          |  | OW HSI = | ·  | OW HSI = | ·  | OW HSI = | ·  |                  |                  |

0 0 0

Project: Little Lake Shoreline Protection/Dedicated Dredging near Project

Round Lake - Area A

Project Area: Fresh.....

Condition: Future With Project

Intermediate. 1,074

|          | ] [  | TY 0                |      | TY 1            |      | TY 3            |      |                      |                  |             |
|----------|--|---------------------|------|-----------------|------|-----------------|------|----------------------|------------------|-------------|
| Variable |  | Value               | SI   | Value           | SI   | Value           | SI   |                      |                  |             |
| V1       | % Emergent   | 50                  | 0.55 | 85              | 0.87 | 90              | 0.91 |                      |                  |             |
| V2       | % Aquatic  | 10                  | 0.19 | 10              | 0.19 | 15              | 0.24 |                      |                  |             |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | %<br>20<br>40<br>40 | 0.44 | <b>%</b><br>100 | 1.00 | <b>%</b><br>100 | 1.00 | 1<br>0<br>0.4<br>0.2 | 1<br>0<br>0<br>0 | 1<br>0<br>0 |
| V4       | %OW <= 1.5ft   | 55                  | 0.72 | 90              | 1.00 | 90              | 1.00 |                      |                  |             |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              | 4                   | 1.00 | 4               | 1.00 | 4               | 1.00 | 1.00                 | 1.00             | 1.00        |
| V6       | Access Value fresh intermediate                                      | 1.00                | 1.00 | 1.00            | 1.00 | 1.00            | 1.00 | 1.00                 | 1.00             | 1.00        |
|          | Emergent Mars  |                     | 0.63 | EM HSI =        | 0.91 | EM HSI =        | 0.94 |                      |                  |             |
|          | Open Water H   | SI =                | 0.38 | OW HSI =        | 0.45 | OW HSI =        | 0.48 | 1                    |                  |             |

Project: Little Lake Shoreline Protection/Dedicated Dredging near FWP

|          |  | TY 5            |      | TY 20                |      |          |    |                  |               |             |
|----------|--|-----------------|------|----------------------|------|----------|----|------------------|---------------|-------------|
| Variable |  | Value           | SI   | Value                | SI   | Value    | SI |                  |               |             |
| V1       | % Emergent   | 91              | 0.92 | 79                   | 0.81 |          |    |                  |               |             |
| V2       | % Aquatic  | 15              | 0.24 | 15                   | 0.24 |          |    |                  |               |             |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | <b>%</b><br>100 | 1.00 | <b>%</b><br>70<br>30 | 0.88 | %        |    | 1<br>0<br>0<br>0 | 1<br>0.6<br>0 | 0<br>0<br>0 |
| V4       | %OW <= 1.5ft   | 85              | 1.00 | 80                   | 1.00 |          |    |                  |               |             |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              | 4               | 1.00 | 4                    | 1.00 |          |    | 1.00             | 1.00          |             |
| V6       | Access Value fresh intermediate                                      | 1.00            | 1.00 | 1.00                 | 1.00 |          |    | 1.00             | 1.00          |             |
|          |  | EM HSI =        | 0.95 | EM HSI =             | 0.86 | EM HSI = |    | ]                |               |             |
|          |  | OW HSI =        | 0.48 | OW HSI =             | 0.48 | OW HSI = |    |                  |               |             |

Project: Little Lake Shoreline Protection/Dedicated Dredging near

FWP

| FVVP     | _   |          |    |          |    |          |    |  |
|----------|---|----------|----|----------|----|----------|----|--|
|          |   |          |    |          |    |          |    |  |
| Variable |   | Value    | SI | Value    | SI | Value    | SI |  |
|          | 0/ 5  |          |    |          |    |          |    |  |
| V1       | % Emergent  |          |    |          |    |          |    |  |
| V2       | % Aquatic   |          |    |          |    |          |    |  |
| V3       | Interspersion Class 1 Class 2 Class 3 Class 4 Class 5 | %        |    | %        |    | %        |    |  |
| V4       | %OW <= 1.5ft  |          |    |          |    |          |    |  |
| V5       | Salinity (ppt)<br>fresh<br>intermediate               |          |    |          |    |          |    |  |
| V6       | Access Value fresh intermediate                       |          |    |          |    |          |    |  |
|          |   | EM HSI = |    | EM HSI = |    | EM HSI = |    |  |
|          |   | OW HSI = |    | OW HSI = |    | OW HSI = |    |  |

0

0 0

0 0

0

0

# **AAHU CALCULATION - EMERGENT MARSH**

Project: Little Lake Shoreline Protection/Dedicated Dredging near

Round Lake - Area A

| Future Witho | out Project |   |      | Total   | Cummulative |
|--------------|-------------|---|------|---------|-------------|
| TY           | Marsh Acres | Х | HSI  | HUs     | HUs         |
| 0            | 532         |   | 0.63 | 336.54  |             |
| 1            | 521         |   | 0.63 | 326.22  | 331.37      |
| 20           | 336         |   | 0.49 | 164.22  | 4578.65     |
|              |             |   |      |         |             |
|              |             |   |      |         |             |
|              |             |   |      |         |             |
|              |             |   |      |         |             |
|              |             |   |      |         |             |
|              |             |   |      |         |             |
|              |             |   |      | AAHUs = | 245.50      |

| Future With    | Project |       | Total  | Cummulative |
|----------------|---------|-------|--------|-------------|
| TY Marsh Acres |         | x HSI | HUs    | HUs         |
| 0              | 532     | 0.63  | 336.54 |             |
| 1              | 315     | 0.91  | 287.11 | 321.91      |
| 3              | 661     | 0.94  | 622.14 | 905.82      |
| 5              | 976     | 0.95  | 924.40 | 1545.92     |
| 20             | 853     | 0.86  | 735.35 | 12422.02    |
|                |         |       |        |             |
|                |         |       |        |             |
|                |         |       |        |             |
|                |         |       |        |             |
| _              |         |       | AAHUs  | 759.78      |

| NET CHANGE IN AAHUS DUE TO PROJECT               |        |
|--|--------|
| A. Future With Project Emergent Marsh AAHUs =    | 759.78 |
| B. Future Without Project Emergent Marsh AAHUs = | 245.50 |
| Net Change (FWP - FWOP) =                        | 514.28 |

AAHU CALCULATION - OPEN WATER

Project: Little Lake Shoreline Protection/Dedicated Dredging near Round Lake - Area A

| Future Witho   | out Project |       | Total        | Cummulative |
|----------------|-------------|-------|--------------|-------------|
| TY Water Acres |             | x HSI | HUs          | HUs         |
| 0              | 542         | 0.38  | 207.99       |             |
| 1              | 553         | 0.38  | 212.21       | 210.10      |
| 20             | 738         | 0.37  | 274.45       | 4630.21     |
|                |             |       |              |             |
|                |             |       |              |             |
|                |             |       |              |             |
|                |             |       |              |             |
|                |             |       |              |             |
|                |             |       |              |             |
|                |             |       | A A LI I a - | 242.02      |

| AAHUs = 242.02 |
|----------------|
|----------------|

| Future With |             |   | Total | Cummulative |         |
|-------------|-------------|---|-------|-------------|---------|
| TY          | Water Acres | Х | HSI   | HUs         | HUs     |
| 0           | 542         |   | 0.38  | 207.99      |         |
| 1           | 54          |   | 0.45  | 24.09       | 121.10  |
| 3           | 71          |   | 0.48  | 34.42       | 58.28   |
| 5           | 98          |   | 0.48  | 47.50       | 81.92   |
| 20          | 221         |   | 0.48  | 105.16      | 1147.74 |
|             |             |   |       |             |         |
|             |             |   |       |             |         |
|             |             |   |       |             |         |
|             |             |   |       |             |         |
|             |             |   |       | AAHUs       | 70.45   |

| NET CHANGE IN AAHUS DUE TO PROJECT           |         |
|--|---------|
| A. Future With Project Open Water AAHUs =    | 70.45   |
| B. Future Without Project Open Water AAHUs = | 242.02  |
| Net Change (FWP - FWOP) =                    | -171.56 |

| TOTAL BENEFITS IN AAHUS DUE TO PROJEC  | CT      |
|--|---------|
| A. Emergent Marsh Habitat Net AAHUs =  | 514.28  |
| B. Open Water Habitat Net AAHUs =      | -171.56 |
| Net Benefits=(2.1xEMAAHUs+OWAAHUs)/3.1 | 293.04  |

Project: Little Lake Shoreline Protection/Dedicated Dredging near Project Area:

Round Lake - Area B

Fresh.....

Condition: Future Without Project Intermediate. 93

|          | ] [  | TY 0                 |      | TY 1                 | TY 1 |          | TY 20 |                      |                      |                  |
|----------|--|----------------------|------|----------------------|------|----------|-------|----------------------|----------------------|------------------|
| Variable |  | Value                | SI   | Value                | SI   | Value    | SI    |                      |                      |                  |
| V1       | % Emergent   | 61                   | 0.65 | 56                   | 0.60 | 0        | 0.10  |                      |                      |                  |
| V2       | % Aquatic  | 0                    | 0.10 | 0                    | 0.10 | 0        | 0.10  |                      |                      |                  |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | <b>%</b><br>80<br>20 | 0.52 | <b>%</b><br>80<br>20 | 0.52 | %        | 0.10  | 0<br>0.6<br>0<br>0.2 | 0<br>0.6<br>0<br>0.2 | 0<br>0<br>0<br>0 |
| V4       | %OW <= 1.5ft   | 50                   | 0.66 | 50                   | 0.66 | 0        | 0.10  |                      |                      |                  |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              | 4                    | 1.00 | 4                    | 1.00 | 4        | 1.00  | 1.00                 | 1.00                 | 1.00             |
| V6       | Access Value fresh intermediate                                      | 1.00                 | 1.00 | 1.00                 | 1.00 | 1.00     | 1.00  | 1.00                 | 1.00                 | 1.00             |
|          | Emergent Mars  |                      | 0.71 | EM HSI =             | 0.68 | EM HSI = | 0.24  |                      |                      |                  |
|          | Open Water H   | SI =                 | 0.30 | OW HSI =             | 0.30 | OW HSI = | 0.23  | <u>I</u>             |                      |                  |

Project: Little Lake Shoreline Protection/Dedicated Dredging near FWOP

| FWOP     | _  |          |    |          |    |          |    |
|----------|--|----------|----|----------|----|----------|----|
|          |  |          |    |          |    |          |    |
| Variable |  | Value    | SI | Value    | SI | Value    | SI |
| 1/4      | ٠, ٦   |          |    |          |    |          |    |
| V1       | % Emergent   |          |    |          |    |          |    |
| V2       | % Aquatic  |          |    |          |    |          |    |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | %        |    | %        |    | %        |    |
| V4       | %OW <= 1.5ft   |          |    |          |    |          |    |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              |          |    |          |    |          |    |
| V6       | Access Value fresh intermediate                                      |          |    |          |    |          |    |
|          |  | EM HSI = |    | EM HSI = |    | EM HSI = |    |
|          |  | OW HSI = |    | OW HSI = |    | OW HSI = |    |

Project: FWOP Little Lake Shoreline Protection/Dedicated Dredging near

| -WOP     | =  |          |    |          |    |          |    | <del></del>      |                  |
|----------|--|----------|----|----------|----|----------|----|------------------|------------------|
| Variable |  | Value    | SI | Value    | SI | Value    | SI |                  |                  |
| V1       | % Emergent   |          |    |          |    |          |    |                  |                  |
| V2       | % Aquatic  |          |    |          |    |          |    |                  |                  |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | %        |    | %        |    | %        |    | 0<br>0<br>0<br>0 | 0<br>0<br>0<br>0 |
| V4       | %OW <= 1.5ft   |          |    |          |    |          |    |                  |                  |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              |          |    |          |    |          |    |                  |                  |
| V6       | Access Value fresh intermediate                                      |          |    |          |    |          |    |                  |                  |
|          |  | EM HSI = | •  | EM HSI = |    | EM HSI = | •  |                  |                  |
|          |  | OW HSI = | ·  | OW HSI = | ·  | OW HSI = | ·  |                  |                  |

0 0 0

Project: Little Lake Shoreline Protection/Dedicated Dredging near Project

Round Lake - Area B

Project Area: Fresh.....

0

0

0

0

0

0

0

Condition: Future With Project Intermediate. 93

|          | ]   | TY 0                 |      | TY 1                 |      | TY 1          |      | TY 20                |                      |                      |  |  |
|----------|---|----------------------|------|----------------------|------|---------------|------|----------------------|----------------------|----------------------|--|--|
| Variable |   | Value                | SI   | Value                | SI   | Value         | SI   |                      |                      |                      |  |  |
| V1       | % Emergent  | 61                   | 0.65 | 61                   | 0.65 | 61            | 0.65 |                      |                      |                      |  |  |
| V2       | % Aquatic   | 0                    | 0.10 | 0                    | 0.10 | 0             | 0.10 |                      |                      |                      |  |  |
| V3       | Interspersion Class 1 Class 2 Class 3 Class 4 Class 5 | <b>%</b><br>80<br>20 | 0.52 | <b>%</b><br>80<br>20 | 0.52 | %<br>80<br>20 | 0.52 | 0<br>0.6<br>0<br>0.2 | 0<br>0.6<br>0<br>0.2 | 0<br>0.6<br>0<br>0.2 |  |  |
| V4       | %OW <= 1.5ft  | 50                   | 0.66 | 50                   | 0.66 | 50            | 0.66 |                      |                      |                      |  |  |
| V5       | Salinity (ppt)<br>fresh<br>intermediate               | 4                    | 1.00 | 4                    | 1.00 | 4             | 1.00 | 1.00                 | 1.00                 | 1.00                 |  |  |
| V6       | Access Value<br>fresh<br>intermediate                 | 1.00                 | 1.00 | 1.00                 | 1.00 | 1.00          | 1.00 | 1.00                 | 1.00                 | 1.00                 |  |  |
|          | Emergent Mars   |                      | 0.71 | EM HSI =             |      | EM HSI =      | 0.71 |                      |                      |                      |  |  |
|          | Open Water H  | ISI =                | 0.30 | OW HSI =             | 0.30 | OW HSI =      | 0.30 | <u> </u>             |                      |                      |  |  |

Project: Little Lake Shoreline Protection/Dedicated Dredging near FWP

|          | il 1   |          |    |          |    | ı        |    |
|----------|--|----------|----|----------|----|----------|----|
| Variable |  | Value    | SI | Value    | SI | Value    | SI |
| V1       | % Emergent   |          |    |          |    |          |    |
| V2       | % Aquatic  |          |    |          |    |          |    |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | %        |    | %        |    | %        |    |
| V4       | %OW <= 1.5ft   |          |    |          |    |          |    |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              |          |    |          |    |          |    |
| V6       | Access Value fresh intermediate                                      |          |    |          |    |          |    |
|          | •  | EM HSI = |    | EM HSI = |    | EM HSI = |    |
|          |  | OW HSI = |    | OW HSI = |    | OW HSI = |    |

Project: FWP Little Lake Shoreline Protection/Dedicated Dredging near

| FVVP     | _   |          |    |          |    |          |    |
|----------|---|----------|----|----------|----|----------|----|
|          |   |          |    |          |    |          |    |
| Variable |   | Value    | SI | Value    | SI | Value    | SI |
|          | 0/ 5  |          |    |          |    |          |    |
| V1       | % Emergent  |          |    |          |    |          |    |
| V2       | % Aquatic   |          |    |          |    |          |    |
| V3       | Interspersion Class 1 Class 2 Class 3 Class 4 Class 5 | %        |    | %        |    | %        |    |
| V4       | %OW <= 1.5ft  |          |    |          |    |          |    |
| V5       | Salinity (ppt)<br>fresh<br>intermediate               |          |    |          |    |          |    |
| V6       | Access Value fresh intermediate                       |          |    |          |    |          |    |
|          |   | EM HSI = |    | EM HSI = | -  | EM HSI = |    |
|          |   | OW HSI = |    | OW HSI = |    | OW HSI = |    |

0

0 0 0

0

0

# **AAHU CALCULATION - EMERGENT MARSH**

Project: Little Lake Shoreline Protection/Dedicated Dredging near

Round Lake - Area B

| Future Witho |             |   | Total | Cummulative |        |
|--------------|-------------|---|-------|-------------|--------|
| TY           | Marsh Acres | Х | HSI   | HUs         | HUs    |
| 0            | 57          |   | 0.71  | 40.55       |        |
| 1            | 53          |   | 0.68  | 36.03       | 38.27  |
| 20           | 0           |   | 0.24  | 0.00        | 267.88 |
|              |             |   |       |             |        |
|              |             |   |       |             |        |
|              |             |   |       |             |        |
|              |             |   |       |             |        |
|              |             |   |       |             |        |
|              |             |   |       |             |        |
|              |             |   |       | AAHUs =     | 15.31  |

| Future With | Project     |       | Total | Cummulative |
|-------------|-------------|-------|-------|-------------|
| TY          | Marsh Acres | x HSI | HUs   | HUs         |
| 0           | 57          | 0.71  | 40.55 |             |
| 1           | 57          | 0.71  | 40.55 | 40.55       |
| 20          | 57          | 0.71  | 40.55 | 770.42      |
|             |             |       |       |             |
|             |             |       |       |             |
|             |             |       |       |             |
|             |             |       |       |             |
|             |             |       |       |             |
|             |             |       |       |             |
|             |             |       | AAHUs | 40.55       |

| NET CHANGE IN AAHUS DUE TO PROJECT               |       |
|--|-------|
| A. Future With Project Emergent Marsh AAHUs =    | 40.55 |
| B. Future Without Project Emergent Marsh AAHUs = | 15.31 |
| Net Change (FWP - FWOP) =                        | 25.24 |

AAHU CALCULATION - OPEN WATER

Project: Little Lake Shoreline Protection/Dedicated Dredging near

| _    |   |  |   |   | _  |
|------|---|--|---|---|----|
| Rour | 1 |  | / | ۱ | п. |
|      |   |  |   |   |    |
|      |   |  |   |   |    |

| Future Witho | out Project |       | Total    | Cummulative |
|--------------|-------------|-------|----------|-------------|
| TY           | Water Acres | x HSI | HUs      | HUs         |
| 0            | 36          | 0.30  | 10.80    |             |
| 1            | 40          | 0.30  | 12.00    | 11.40       |
| 20           | 93          | 0.23  | 21.13    | 326.94      |
|              |             |       |          |             |
|              |             |       |          |             |
|              |             |       |          |             |
|              |             |       |          |             |
|              |             |       |          |             |
|              |             |       |          |             |
|              |             |       | AAUIIc - | 16 02       |

| 1 | AAHUs = | 16.92 |
|---|---------|-------|
|---|---------|-------|

| Future With | Future With Project |   |      | Total | Cummulative |
|-------------|---------------------|---|------|-------|-------------|
| TY          | Water Acres         | Х | HSI  | HUs   | HUs         |
| 0           | 36                  |   | 0.30 | 10.80 |             |
| 1           | 36                  |   | 0.30 | 10.80 | 10.80       |
| 20          | 36                  |   | 0.30 | 10.80 | 205.18      |
|             |                     |   |      |       |             |
|             |                     |   |      |       |             |
|             |                     |   |      |       |             |
|             |                     |   |      |       |             |
|             |                     |   |      |       |             |
|             |                     |   | •    |       |             |
|             |                     | - | •    | AAHUs | 10.80       |

| NET CHANGE IN AAHUS DUE TO PROJECT           |       |
|--|-------|
| A. Future With Project Open Water AAHUs =    | 10.80 |
| B. Future Without Project Open Water AAHUs = | 16.92 |
| Net Change (FWP - FWOP) =                    | -6.12 |

| TOTAL BENEFITS IN AAHUS DUE TO PROJECT |       |  |  |  |  |
|--|-------|--|--|--|--|
| A. Emergent Marsh Habitat Net AAHUs =  | 25.24 |  |  |  |  |
| B. Open Water Habitat Net AAHUs =      | -6.12 |  |  |  |  |
| Net Benefits=(2.1xEMAAHUs+OWAAHUs)/3.1 | 15.13 |  |  |  |  |

Project: Little Lake Shoreline Protection/Dedicated Dredging near Project Area:

Round Lake - Area C

Fresh.....

Condition: Future Without Project Intermediate. 206

|          | ] [  | TY 0                 |      | TY 1           |      | TY 20    |      |                    |                    |                  |
|----------|--|----------------------|------|----------------|------|----------|------|--------------------|--------------------|------------------|
| Variable |  | Value                | SI   | Value          | SI   | Value    | SI   |                    |                    |                  |
| V1       | % Emergent   | 67                   | 0.70 | 64             | 0.68 | 0        | 0.10 |                    |                    |                  |
| V2       | % Aquatic  | 0                    | 0.10 | 0              | 0.10 | 0        | 0.10 |                    |                    |                  |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | <b>%</b><br>75<br>25 | 0.80 | <b>%</b><br>70 | 0.76 | %        | 0.10 | 1<br>0<br>0<br>0.2 | 1<br>0<br>0<br>0.2 | 0<br>0<br>0<br>0 |
| V4       | %OW <= 1.5ft   | 5                    | 0.16 | 4              | 0.15 | 0        | 0.10 |                    |                    |                  |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              | 4                    | 1.00 | 4              | 1.00 | 4        | 1.00 | 1.00               | 1.00               | 1.00             |
| V6       | Access Value<br>fresh<br>intermediate                                | 1.00                 | 1.00 | 1.00           | 1.00 | 1.00     | 1.00 | 1.00               | 1.00               | 1.00             |
|          | Emergent Mars  |                      | 0.78 | EM HSI =       | 0.76 | EM HSI = |      |                    |                    |                  |
|          | Open Water H   | SI =                 | 0.28 | OW HSI =       | 0.28 | OW HSI = | 0.23 | <u> </u>           |                    |                  |

Project: Little Lake Shoreline Protection/Dedicated Dredging near FWOP

| WOP      |  |          |    | 1        |          | ir       |          |
|----------|--|----------|----|----------|----------|----------|----------|
| Variable |  | Value    | SI | Value    | SI       | Value    | SI       |
| Variable |  | Value    |    | Value    | <u> </u> | Value    | <u> </u> |
| V1       | % Emergent   |          |    |          |          |          |          |
| V2       | % Aquatic  |          |    |          |          |          |          |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | %        |    | %        |          | %        |          |
| V4       | %OW <= 1.5ft   |          |    |          |          |          |          |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              |          |    |          |          |          |          |
| V6       | Access Value fresh intermediate                                      |          |    |          |          |          |          |
|          |  | EM HSI = |    | EM HSI = |          | EM HSI = |          |
|          | Ī  | OW HSI = |    | OW HSI = |          | OW HSI = |          |

Project: FWOP Little Lake Shoreline Protection/Dedicated Dredging near

| -WOP     | =  |          |    |          |    |          |    | <del></del>      |                  |
|----------|--|----------|----|----------|----|----------|----|------------------|------------------|
| Variable |  | Value    | SI | Value    | SI | Value    | SI |                  |                  |
| V1       | % Emergent   |          |    |          |    |          |    |                  |                  |
| V2       | % Aquatic  |          |    |          |    |          |    |                  |                  |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | %        |    | %        |    | %        |    | 0<br>0<br>0<br>0 | 0<br>0<br>0<br>0 |
| V4       | %OW <= 1.5ft   |          |    |          |    |          |    |                  |                  |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              |          |    |          |    |          |    |                  |                  |
| V6       | Access Value fresh intermediate                                      |          |    |          |    |          |    |                  |                  |
|          |  | EM HSI = | •  | EM HSI = |    | EM HSI = | •  |                  |                  |
|          |  | OW HSI = | ·  | OW HSI = | ·  | OW HSI = | ·  |                  |                  |

0 0 0

Project: Little Lake Shoreline Protection/Dedicated Dredging near Project

Round Lake - Area C

Project Area: Fresh.....

Condition: Future With Project

Intermediate. 206

|          | ]   | TY 0          |      | TY 1                 |      | TY 20         |      |                    |                    |                    |
|----------|---|---------------|------|----------------------|------|---------------|------|--------------------|--------------------|--------------------|
| Variable |   | Value         | SI   | Value                | SI   | Value         | SI   |                    |                    |                    |
| V1       | % Emergent  | 67            | 0.70 | 67                   | 0.70 | 67            | 0.70 |                    |                    |                    |
| V2       | % Aquatic   | 0             | 0.10 | 0                    | 0.10 | 0             | 0.10 |                    |                    |                    |
| V3       | Interspersion Class 1 Class 2 Class 3 Class 4 Class 5 | %<br>75<br>25 | 0.80 | <b>%</b><br>75<br>25 | 0.80 | %<br>75<br>25 | 0.80 | 1<br>0<br>0<br>0.2 | 1<br>0<br>0<br>0.2 | 1<br>0<br>0<br>0.2 |
| V4       | %OW <= 1.5ft  | 5             | 0.16 | 5                    | 0.16 | 5             | 0.16 |                    |                    |                    |
| V5       | Salinity (ppt)<br>fresh<br>intermediate               | 4             | 1.00 | 4                    | 1.00 | 4             | 1.00 | 1.00               | 1.00               | 1.00               |
| V6       | Access Value fresh intermediate                       | 1.00          | 1.00 | 1.00                 | 1.00 | 1.00          | 1.00 | 1.00               | 1.00               | 1.00               |
|          | Emergent Mar  |               | 0.78 | EM HSI =             | 0.78 | EM HSI =      |      |                    |                    |                    |
|          | Open Water H  | SI =          | 0.28 | OW HSI =             | 0.28 | OW HSI =      | 0.28 |                    |                    |                    |

Project: Little Lake Shoreline Protection/Dedicated Dredging near FWP

| FVVF     | <b>=</b> 1   |          |    | ŭ-       |    | i-       |    |
|----------|--|----------|----|----------|----|----------|----|
|          |  |          |    |          |    |          |    |
| Variable |  | Value    | SI | Value    | SI | Value    | SI |
|          |  |          |    |          |    |          |    |
| V1       | % Emergent   |          |    |          |    |          |    |
| V2       | % Aquatic  |          |    |          |    |          |    |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | %        |    | %        |    | %        |    |
| V4       | %OW <= 1.5ft   |          |    |          |    |          |    |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              |          |    |          |    |          |    |
| V6       | Access Value fresh intermediate                                      |          |    |          |    |          |    |
|          |  | EM HSI = |    | EM HSI = |    | EM HSI = |    |
|          |  | OW HSI = |    | OW HSI = |    | OW HSI = |    |

0 0 0 0 0 0 0 0 0 0 0 0 Project: FWP Little Lake Shoreline Protection/Dedicated Dredging near

| -VVP     | =1 .   |          |    |          |    |          |    |
|----------|--|----------|----|----------|----|----------|----|
|          |  |          |    |          |    |          |    |
| Variable |  | Value    | SI | Value    | SI | Value    | SI |
| V1       | % Emergent   |          |    |          |    |          |    |
| V2       | % Aquatic  |          |    |          |    |          |    |
| V3       | Interspersion<br>Class 1<br>Class 2<br>Class 3<br>Class 4<br>Class 5 | %        |    | %        |    | %        |    |
| V4       | %OW <= 1.5ft   |          |    |          |    |          |    |
| V5       | Salinity (ppt)<br>fresh<br>intermediate                              |          |    |          |    |          |    |
| V6       | Access Value fresh intermediate                                      |          |    |          |    |          |    |
|          |  | EM HSI = |    | EM HSI = |    | EM HSI = |    |
|          |  | OW HSI = |    | OW HSI = | •  | OW HSI = | •  |

0

0 0

0

0

# **AAHU CALCULATION - EMERGENT MARSH**

Project: Little Lake Shoreline Protection/Dedicated Dredging near

Round Lake - Area C

| Future Without | out Project |   |      | Total   | Cummulative |
|----------------|-------------|---|------|---------|-------------|
| TY             | Marsh Acres | Х | HSI  | HUs     | HUs         |
| 0              | 139         |   | 0.78 | 108.40  |             |
| 1              | 131         |   | 0.76 | 99.14   | 103.74      |
| 20             | 0           |   | 0.24 | 0.00    | 725.94      |
|                |             |   |      |         |             |
|                |             |   |      |         |             |
|                |             |   |      |         |             |
|                |             |   |      |         |             |
|                |             |   |      |         |             |
|                |             |   |      |         |             |
|                |             |   |      | AAHUs = | 41.48       |

| Future With | Project     |       | Total  | Cummulative |
|-------------|-------------|-------|--------|-------------|
| TY          | Marsh Acres | x HSI | HUs    | HUs         |
| 0           | 139         | 0.78  | 108.40 |             |
| 1           | 139         | 0.78  | 108.40 | 108.40      |
| 20          | 139         | 0.78  | 108.40 | 2059.59     |
|             |             |       |        |             |
|             |             |       |        |             |
|             |             |       |        |             |
|             |             |       |        |             |
|             |             |       |        |             |
|             | ·           |       |        |             |
|             |             |       | AAHUs  | 108.40      |

| NET CHANGE IN AAHUS DUE TO PROJECT               |        |
|--|--------|
| A. Future With Project Emergent Marsh AAHUs =    | 108.40 |
| B. Future Without Project Emergent Marsh AAHUs = | 41.48  |
| Net Change (FWP - FWOP) =                        | 66.92  |

# **AAHU CALCULATION - OPEN WATER**

**Project:** Little Lake Shoreline Protection/Dedicated Dredging near Round Lake - Area C

| Future Witho | out Project |       | Total | Cummulative |
|--------------|-------------|-------|-------|-------------|
| TY           | Water Acres | x HSI | HUs   | HUs         |
| 0            | 67          | 0.28  | 18.98 |             |
| 1            | 75          | 0.28  | 20.96 | 19.97       |
| 20           | 206         | 0.23  | 46.80 | 665.38      |
|              |             |       |       |             |
|              |             |       |       |             |
|              |             |       |       |             |
|              | `           |       |       |             |
|              | `           |       |       |             |
|              |             |       |       |             |

AAHUs =

34.27

| Future With | Project     |       | Total | Cummulative |
|-------------|-------------|-------|-------|-------------|
| TY          | Water Acres | x HSI | HUs   | HUs         |
| 0           | 67          | 0.28  | 18.98 |             |
| 1           | 67          | 0.28  | 18.98 | 18.98       |
| 20          | 67          | 0.28  | 18.98 | 360.54      |
|             |             |       |       |             |
|             |             |       |       |             |
|             |             |       |       |             |
|             |             |       |       |             |
|             |             |       |       |             |
|             | `           |       |       |             |
|             |             |       | ΔΔΗΠς | 18 98       |

| NET CHANGE IN AAHUS DUE TO PROJECT           |        |
|--|--------|
| A. Future With Project Open Water AAHUs =    | 18.98  |
| B. Future Without Project Open Water AAHUs = | 34.27  |
| Net Change (FWP - FWOP) =                    | -15.29 |

| TOTAL BENEFITS IN AAHUS DUE TO PROJECT |        |
|--|--------|
| A. Emergent Marsh Habitat Net AAHUs =  | 66.92  |
| B. Open Water Habitat Net AAHUs =      | -15.29 |
| Net Benefits=(2.1xEMAAHUs+OWAAHUs)/3.1 | 40.40  |