

ADDENDUM No. 1 TO BID DOCUMENTS FOR THE

**BRADY CANAL HYDROLOGIC RESTORATION (TE-0028)
2018 MAINTENANCE EVENT
TERREBONNE PARISH, LOUISIANA**



**STATE OF LOUISIANA
COASTAL PROTECTION AND RESTORATION AUTHORITY**

MAY 13th, 2019

The interpretations, corrections, or changes in this addendum supersede the requirements in the Bid Documents dated March 2019, and stamped and sealed by the Engineer of Record on May 20, 2019. The Successful Bidder shall be issued a revised set of Contract Documents.

Bidders shall acknowledge receipt of this addendum in the Louisiana Public Work Bid Form.

Brady Canal Hydrologic Restoration 2018 Maintenance Event (TE-28)

Addendum No. 1

May 17, 2019

All revisions are indicated in **bold**. The following items are included in Addendum No. 1 to the Brady Canal Hydrologic Restoration 2018 Maintenance Event (TE-28), dated March 2019.

Specifications:

SECTION TS-4 – MECHANICAL DREDGING AND FILL PLACEMENT, Item 4.2 Dredge Location Control:

Delete this item in its entirety and replace with the following:

“The Contractor is required to utilize a differential global positioning system (DGPS) to accurately and continuously track the position of the dredge while dredging the borrow areas. Contractor shall verify all dredge operations are completed with the horizontal and vertical work area limits. The Engineer or Resident Project Representative shall be allowed to board the dredge and observe dredging operations. The Contractor is required to calibrate the DGPS equipment as per manufacturer’s specifications. The calibrations records shall be included in the Process Surveys.”

Pre-Bid Meeting Minutes, Question and Answer Clarifications, and Attendance Sign-In Sheet:

Attached - Seven (7) Pages.

End of Addendum No.1

ALL SOUTH CONSULTING ENGINEERS, LLC

652 Papworth Avenue
Metairie, LA 70005
Tel (504) 322-2783 - Fax (504) 322-2787

M E E T I N G R E P O R T

Attendees: Sign-In Sheet Attached
Location: CPRA Thibodaux Regional Office, 1440 Tiger Dr.
Date: May 9, 2019, 10:00 AM
Re: Pre-Bid Meeting, Brady Canal Hydrologic Restoration 2018 Maintenance Event (TE-28)

The purpose of this meeting was to hold a mandatory pre-bid meeting for the referenced project (“Brady Canal”).

Items discussed were as follows:

- Discussion at the pre-bid meeting and pre-bid site tour are for informational purposes only and do not constitute a formal response or constitute a change to the contract documents. Formal responses to questions and RFI’s will be made by addenda only.
- The work consists of providing all equipment, labor, and materials necessary to mechanically dredge material from the Jug Lake (approx. 13,785 LF) and Bayou Carencro (approx. 540 LF) borrow areas and placed on adjacent bank lines to offset existing scour effects. Material shall be mechanically placed on the bank lines per typical sections and cross-sections contained in the Project Documents.

Project includes one Alternate, to dredge and place additional material along the Jug Lake bank line (10,000 CY -- Approx. 1,000 LF).

- Engineer’s Estimate of Probable Construction Cost: \$529,510.17
- Bid Opening: May 22, 2019, 2018 at 2:00 PM
- Deadline for questions and RFI’s: 2:00 PM on Monday, May 13, 2019. All questions should be directed to Ms. Allison Richard at cpra.bidding@la.gov
- Contract Time: 150 Calendar Days
- Liquidated Damages: \$1,500 per calendar day
- Plan documents can be found online.
- The Project Team includes CPRA (Mr. Brian Babin and Mr. Brandon Carreras) and All South Consulting Engineers (Mr. Jarret Bauer).
- Permits: Project is permitted as a Maintenance Dredging project for TE-28. These documents are included in the specs.
- Expected weather days are noted in GP-7 (per month). Additional weather days will only be considered once minimums are met.

Addendum No. 1

Brady Canal Hydrologic Restoration 2018 Maintenance Event (TE-28)

ALL SOUTH CONSULTING ENGINEERS, LLC

652 Papworth Avenue
Metairie, LA 70005
Tel (504) 322-2783 - Fax (504) 322-2787

- Work Plan must be submitted to work beginning onsite. Work Plan is detailed in General Provision 8, as well as other locations in the project specifications
- Dredging: Only mechanical dredging shall be allowed. Dredging tolerance allows for +1.0' of over-dredging beyond Plan inverts at no-additional pay. No final grading shall be required.
- Surveys: Pre-construction, Magnetometer, Process, and As-Built surveys will be required of the borrow area. Process surveys may be used as the As-Built survey upon approval. Contractor shall also be required to make one, centerline survey of placement area.
- Placement: Material placement tolerance will be +1.0' (vertical) and within a 30' – 50' (horizontal) limit based on typical sections. Material shall be placed on the “Backside” or “Frontside” per Project Typical Sections. Clearing and grubbing is not required. The landowner is aware that damage to existing vegetation may occur during placement. Contractor shall only be required to address egregious damages.
- Dikes are noted “as req'd” to contain material. Engineer may require dike upon field inspection.

Questions and Answers

Question: *The project specifications under Section TS-4, Item 4.2 require dredge depth to be tracked and recorded while dredging within borrow areas. Will this be required?*

Answer: *This requirement has been removed from the Project Documents as part of the Addendum. Depth of dredge shall be verified via process surveys.*

Question: *Can you clarify locations where signage will be required?*

Answer: *Signage will be required (at a minimum) at start and end of the each work area, as well as along any intermediate access points that may be contained within the work area. It is in the Contractor's interest to provide additional signage along the project for workplace safety, but this additional signage is not required.*

Question: *Will the Contractor be allowed to clear existing vegetation to perform the centerline survey of the placement area.*

Answer: *Contractor should minimize clearing but will be allowed to clear the placement area for survey access. Clearing shall be limited to reasonable access path along embankment centerline.*

Question: *Are construction funds available to complete this project and when does CPRA anticipate the project will begin?*

Answer: *Yes, construction funds are currently available. Notice to proceed is anticipated for the end of July 2019.*

ALL SOUTH CONSULTING ENGINEERS, LLC

652 Papworth Avenue
Metairie, LA 70005
Tel (504) 322-2783 - Fax (504) 322-2787

Question: *Project documents indicate dikes are to be built “as required.” Has there been any consideration to providing a separate line item for dike construction? Bids for dredging may fluctuate based on the need to provide a marsh buggy for dike construction.*

Answer: *A separate line item will not be included for dike construction. Dikes are noted “as required” in the project documents. If the Contractor or Engineer determines dikes are required, dikes may be constructed by the Contractor’s existing dragline or other dredge equipment using the existing earthen embankment material. A separate marsh buggy may be used at the Contractor’s discretion, but will not be required to place and shape the dikes.*

Question: *Can the source for material for the containment dikes be clarified? On page 53 of the specs under 4.3 Material Placement, it states dikes are to be constructed prior to placing dredge material and the containment dikes may be constructed from the existing earthen embankment. At the pre-bid meeting it seemed the source for material for the dikes would be the Embankment Borrow Area.*

Answer: *The source for the containment dike material may be the existing earthen embankment. There is no requirement that the dikes shall be constructed from the Embankment Borrow Area.*

PRE-BID MEETING ATTENDANCE RECORD

BRADY CANAL HYDROLOGIC RESTORATION (TE-28) - 2018 MAINTENANCE PROJECT

AGENCY: COASTAL PROTECTION AND RESTORATION AUTHORITY

DATE: May 9, 2019 @ 10:00 AM

PLEASE PRINT CLEARLY

NAME (print & signature)	COMPANY/ADDRESS	PHONE NO. FAX NO.	E-MAIL
JARRET BAUER <i>JRB</i>	<u>All South Louisiana</u> <u>652 PARDON AVE.</u> <u>METairie, LA 70005</u>	504-322-2783 504-322-2787	JBAUER@ASCELLC.COM
BRANDON CARRERAS <i>Brandon Carreras</i>	<u>CPRR - TRO</u>	985-444-5342	Brandon.Carreras@LA.GOV
Brian Babin <i>B. Babin</i>	<u>CPRR - TRO</u> <u>1440 Tiger Drive</u> <u>Tribidoux, LA 70301</u>	985-447-0956	brian.babin@la.gov
Kevin Dupre <i>Kevin Dupre</i>	<u>Dupre Brothers Const</u> <u>114 Dickson Rd.</u> <u>Houma, LA 70363</u>	985-879-4440 985-868-0815	kevinp@duprebros.com
JIM FURLETTE <i>J. Furlette</i>	<u>DIAMOND SERVICES CORP</u> <u>PO BOX 1286</u> <u>MORNING CITY, LA 70381</u>	985 631-2187 985 631-4564	JIM@DSCGOM.COM DSCGOM
Mike Maycox <i>Mike Maycox</i>	<u>Southern Delta Const</u> <u>PO Box 1101</u> <u>Vicksburg Ms 39181</u>	985 209-9884	m_maycox@bollsouth.net
TROY M. LOMBARDI <i>Troy M. Lombardi</i>	<u>Benny Bros.</u> <u>1414 River Rd</u> <u>Berwick, LA 70342</u>	985-384-8770 985-384-8779	troy@bbgci.com

PRE-BID MEETING ATTENDANCE RECORD

BRADY CANAL HYDROLOGIC RESTORATION (TE-28) – 2018 MAINTENANCE PROJECT

AGENCY: COASTAL PROTECTION AND RESTORATION AUTHORITY

DATE: May 9, 2019 @ 10:00 AM

PLEASE PRINT CLEARLY

NAME (print & signature)	COMPANY/ADDRESS	PHONE NO. FAX NO.	E-MAIL
Cecil Thibodeaux <i>Cecil Thibodeaux</i>	Crosby Dredging PO BOX 279 Golden Meadow LA	318-655-6313	jcaldwell@CrosbyDredging.com
Kent Gravois <i>Kent Gravois</i>	Portchartrain Partners LLC 239 South Clark St New Orleans 70119	504 325 4321	KentGravois@portchartrain.com
DAVID CROZICHAN <i>David Crozichan</i>	206 INDUSTRIAL AVE HOUMA - LA 70363	985-446-1314	PATTIC@LOWLANDCCI.COM
Perry Autin <i>Perry Autin</i>	2018 Engineers PC Bellechasse LA 70037	504-458-0157	Perry@MarshBuggies.com

PRE-BID MEETING ATTENDANCE RECORD

BRADY CANAL HYDROLOGIC RESTORATION (TE-28) – 2018 MAINTENANCE PROJECT

AGENCY: COASTAL PROTECTION AND RESTORATION AUTHORITY

DATE: May 9, 2019 @ 10:00 AM

PLEASE PRINT CLEARLY

NAME (print & signature)	COMPANY/ADDRESS	PHONE NO. FAX NO.	E-MAIL
David DeTiveaux <i>David DeTiveaux</i>	Dean Equipment 2240 Pelens Rd Harvey La 70058	504- 390 7498	dauiddetiveaux@deandigs.com
Robert Sarron <i>Robt Sar</i>	Patrol Construction 1026 Toby Manton Rd Duson, LA 70529	(337) 935-6917	robert@patrol-construction.com
JERRY DEVILLE <i>Jr Dev</i>	WEEKS MARINE, INC. 304 GAILLE DR. COUNINGTON LA 70433	985-875-2500	JCDEVILLE@WEEKSMARINE.COM
Tim Vestal <i>Tim Vestal</i>	WEEKS MARINE INC. _____ _____	985-991-9053	TVESTAL@WEEKSMARINE.COM
	_____ _____		
	_____ _____		
	_____ _____		

PRE-BID MEETING ATTENDANCE RECORD

BRADY CANAL HYDROLOGIC RESTORATION (TE-28) - 2018 MAINTENANCE PROJECT

AGENCY: COASTAL PROTECTION AND RESTORATION AUTHORITY

DATE: May 9, 2019 @ 10:00 AM

PLEASE PRINT CLEARLY

NAME (print & signature)	COMPANY/ADDRESS	PHONE NO. FAX NO.	E-MAIL
MIKE NITSKA <i>Mike Nitska</i>	HYDROTERRA TECH 202 JACOBS RUN SCOTT LA 70587	337-315-2190	MIKE.NITSKA @ HYDROTERRATEC.COM
Grady Burge <i>Grady Burge</i>	River Road const 812 BOULFOUCA LA MORNINGVILLE, GA 30471	601-590-1455	JLorenz@gmail.com

