

**ADDENDUM #1 TO BID DOCUMENTS  
WHISKEY ISLAND BACK BARRIER VEGETATIVE PROJECT (TE-50)  
FILE NUMBER: Q 27516 DL  
SOLICITATION NUMBER: 2235334**

**The clarifications, responses to Contractor questions and revisions to the Plans and Specifications provided in this addendum supersede the requirements of the Plans and Specifications dated May 2009.**

**The bidder shall acknowledge this addendum by completing page four of the specifications and submitting it with their bids.**

**1. General:**

- 1.1 Seahore Dropseed (*Sporobolus virginicus*) has been removed from this bid. The quantity for Bitter Panicum (*Panicum amarum*) has been increased to 23,400. A revised Schedule of Bid Items (Page 3 of the Specifications) is included in Attachment A. This revised Schedule of Bid Items must be completed and attached to the bid submitted to the Office of State Purchasing in order for the bid to be considered.

**2. Questions:**

2.1 Black Lake Marsh Inc.

- 2.1.1 Question: Page 3 of the Front End Documents. It is noted that 'Completion Time' is 210 days. Page 26 of the Bid package. It is noted in SP-3 that the 'End of Contract Time' is 250 calendar days. What is the contract time?

Response: Completion Time is 250 calendar days after the Notice to Proceed.

**3. Revisions to the Specifications:**

- 3.1 Completion Time (Page 3 of Front End Documents) - The section is replaced in its entirety with the following:

**COMPLETION TIME:**

*The Bidder shall agree to fully complete the contract within 250 consecutive calendar days for the bid, subject to such extensions as may be granted under Section Extension of Contract Time of the General Provisions, and acknowledges that this construction time will start on or before the date specified in the written "Notice to Proceed" from the Owner.*

3.2 SP-2 Work To Be Done - Replace the fourth paragraph with the following:

*Under the Bid of this Contract, the Contractor shall supply, transport, store, and plant approximately 50,000 vegetative plugs of Smooth Cordgrass (Spartina alterniflora 'Vermilion'), 1,000 four (4) inch containers of Black Mangroves (Avicennia germinans 'Pelican'), 23,400 four (4) inch containers of Bitter Panicum (Panicum amarum var. amarum 'Fourchon'), 7,800 four (4) inch containers of Seacoast Bluestem (Schizachyrium maritimum 'Timbalier'), 7,800 four (4) inch containers of Marshhay Cordgrass (Spartina patens 'Gulf Coast'), and 7,800 one (1) trade gallon containers of Sea Oats (Uniola paniculata 'Caminada') plants along the dune and marsh platforms as specified. Date and time for delivery and planting shall be coordinated with the Owner.*

3.3 TS-1 General Requirements – Replace sections 1.1.1 and 1.1.2 with the following:

*1.1.1 The Contractor shall supply, transport, store and plant approximately 50,000 vegetative plugs of Smooth Cordgrass (Spartina alterniflora 'Vermilion'), 1,000 four (4) inch containers of Black Mangroves (Avicennia germinans 'Pelican'), 23,400 four (4) inch containers of Bitter Panicum (Panicum amarum var. amarum 'Fourchon'), 7,800 four (4) inch containers of Seacoast Bluestem (Schizachyrium maritimum 'Timbalier'), 7,800 four (4) inch containers of Marshhay Cordgrass (Spartina patens 'Gulf Coast'), and 7,800 one (1) trade gallon containers of Sea Oats (Uniola paniculata 'Caminada') ) plants on the marsh platform and containment dikes at the Whiskey Island Back Barrier Project as specified. Date and time for delivery and planting shall be coordinated with the Owner.*

*1.1.2 The Black Mangroves, Bitter Panicum, Seacoast Bluestem, Marshhay Cordgrass and Sea Oats shall be planted five (5) feet and the Smooth Cordgrass shall be planted three (3) feet on center in rows as shown on the Plans. The Owner reserves to the right to modify the spacing and location of plants and rows; such modifications shall be accomplished through Change or Field Orders where appropriate.*

3.4 TS-4 Plant Type – Delete section 4.5 in its entirety

**ATTACHMENT A**

**Revised Schedule of Bid Items  
(Bid Package Page 3)**

