

State of Louisiana

Coastal Protection and Restoration Authority (CPRA)

2020 Operations, Maintenance, and Monitoring Report

for

Marsh Island Hydrologic Restoration

State Project Number TV-14 Priority Project List 6

June 2020 Iberia Parish

Prepared by:

Mark Mouledous And Dion Broussard, P.E.

Operations Division Lafayette Regional Office 635 Cajundome Boulevard Lafayette, LA 70506



Suggested Citation:

Mouledous, M. and D. Broussard 2020. 2020 Operations, Maintenance, and Monitoring Report for Marsh Island Hydrologic Restoration (TV-14), Coastal Protection and Restoration Authority of Louisiana, Lafayette, Louisiana. 27pp and Appendices.



ii

2020 Operations, Maintenance, and Monitoring Report For Marsh Island Hydrologic Restoration (TV-14)

Table of Contents

I.	Introduction	1
II.	Maintenance Activity	4
	a. Project Feature Inspection Procedures	
	b. Inspection Results	
	c. Maintenance Recommendations	
	i. Immediate/Emergency	
	ii. Programmatic/Routine	
	d. Maintenance History	
III.	Operation Activity	7
	a. Operation Plan	7
	b. Actual operations	7
IV.	Monitoring Activity	
	a. Monitoring Goals	
	b. Monitoring Elements	
	c. Monitoring Results and Discussion	
	Aerial Photography	
	Shoreline Position	.18
	Water Level	.20
	Submerged Aquatic Vegetation	.21
• •		~ (
V.	Conclusions	
	a. Project Effectiveness	
	b. Recommended Improvements	
	c. Lessons Learned	
	d. End of Project Life	.25
VI	Literature Cited	26
V 1.		.20
VI	I. Appendices	.28
	a. Appendix A (Inspection Photographs)	
	b. Appendix B (Three Year Budget Projection)	
	c. Appendix C (Field Inspection Notes)	
	d. Appendix D (Constructed Project Features Map)	.47





Preface

This report includes monitoring data collected through December 2019, and annual Maintenance Inspections through May 2020.

The 2020 report is the 7th and final report in a series of reports. For additional information on lessons learned, recommendations and project effectiveness please refer to previous OM&M reports (2004, 2005, 2007, 2011, 2014 and 2018) on the CPRA web site at <u>http://coastal.Louisiana.gov/</u>. These reports and others are available for download at the following website: <u>http://cims.coastal.la.gov</u>.

I. Introduction

The Marsh Island Hydrologic Restoration Project was proposed on the 6th priority list of the Coastal Wetlands Planning, Protection, and Restoration Act (CWPPRA) and is co-sponsored by the United States Army Corps of Engineers (USACE) and the Coastal Protection and Restoration Authority of Louisiana (CPRA). The project is located in Iberia Parish, approximately six miles south of Cypremort Point. The project area encompasses approximately 7,310 acres (2,958 ha) of wetlands on the northeast tip of Marsh Island, east of Bayou Blanc (Figure 1). It comprises 4,290 acres (1,736 ha) of brackish marsh and 3,020 acres (1,222 ha) of open water, based on the Louisiana Department of Natural Resource's GIS data for 2004 (LDNR 2004). Common plant species found in the project area include *Juncus roemerianus* (needlegrass rush), *Spartina patens* (saltmeadow cordgrass), *Bolboschoenus maritimus* (cosmopolitan bulrush), *Schoenoplectus americanus* (chairmaker's bulrush), *Spartina alterniflora* (saltmarsh cordgrass), and *Vigna luteola* (hairypod cowpea) (United States Department of Agriculture, Natural Resources Conservation Service 2002, Chabreck and Linscombe 1988).

Between 1930 and the present, the hydrology of Marsh Island has changed due to tidal influenced erosion, subsidence, and oil and gas exploration (Orton 1959, SCS 1978). Several oil field canals were constructed to facilitate oil and gas exploration in the project area during the 1950's. Recent deterioration and subsidence of the spoil banks deposited in the 1950's have resulted in cuts in the spoil banks that have become conduits for rapid tidal exchanges between the surrounding bays and the interior marshes. These rapid exchanges have resulted in tidal scouring and the loss of marsh vegetation through erosion and subsidence. Lake Sand and a number of interior lakes also supported a significant amount of submerged aquatic vegetation (SAV). Today these lakes are almost devoid of SAV, presumably due to the effects of increased tidal exchange and increased turbidity. Erosion has also lead to the deterioration of the northeast end of Marsh Island and the north rim of Lake Sand, leaving exposed a highly organic brackish marsh.

During the life of the 20 year project, 408 acres (168 ha) of wetlands will be protected (USACE 1994). The project consists of the construction of 9 closures in oil and gas canals at the northeast end of Marsh Island and free-standing rock breakwaters to isolate Lake Sand from Vermilion Bay and to provide shoreline protection to the northeastern shoreline of Marsh Island (Figure





1). Project construction began on July 25, 2001 with the construction of approximately 4,000 linear feet (1291 m) of rock breakwater to protect the north shoreline of Lake Sand. A total of seven canals were plugged with rock armor while one was plugged with an earthen closure only. An additional closure, constructed of painted steel sheetpile and rock armor, was constructed at the mouth of an oil exploration canal on the eastern end of the project area. Construction of the \$2.9 million project was completed on December 12, 2001.

Hurricane Rita struck the coast of southwestern Louisiana on September 24, 2005 with a maximum storm surge of 10 ft (3.1 m) in the TV-14 project area (FEMA 2006). USGS calculated the amount of land that changed to water resulting from the storm to be 98 square miles in southwestern Louisiana, 5 square miles in the Teche/Vermilion basin (Barras 2006).

Hurricane Ike struck near Galveston, Texas on September 13, 2008. A maximum storm surge of 7 - 8 ft (2.1 - 2.4 m) NAVD 88 was reported near the TV-14 project area (East et al. 2008).

The East Marsh Island Marsh Creation Project (TV-21) was constructed within the TV-14 project area in September 2010 (Figure 1). The project consisted of the addition of sediment hydraulically dredged from East Cote Blanche Bay to create 362 acres (146.5 ha) of contained marsh and 797 acres of un-contained/nourished marsh. The primary purpose of the project is to restore emergent marsh habitat that was lost due to hurricane damage. The TV-21 project provides a synergistic effect with the TV-14 project.








Figure 1. Marsh Island Hydrologic Restoration (TV-14) project boundary and features.





II. Maintenance Activity

a. Project Feature Inspection Procedures

The purpose of the annual inspection of the Marsh Island Hydrologic Restoration Project (TV-14) is to evaluate the constructed project features to identify any deficiencies and prepare a report detailing the condition of project features and recommended corrective actions needed. Should it be determined that corrective actions are needed, CPRA shall provide, in the report, a detailed cost estimate for engineering, design, supervision, inspection, and construction contingencies, and an assessment of the urgency of such repairs. The annual inspection report also contains a summary of maintenance projects which were completed since completion of constructed project features and an estimated projected budget for the upcoming three (3) years for operation, maintenance and rehabilitation. The three (3) year projected operation and maintenance projects completed since completed since completed since and maintenance projects completed since completed since completed since completed since projects are outlined in Section IV.

An inspection of the Marsh Island Hydrologic Restoration Project (TV-14) has not been held since May 16, 2017. The USACE and CPRA mutually agreed that no further maintenance would be done prior to project closeout, and a project extension would not be requested. Therefore, annual inspections were not continued beyond 2017.

The 2017 field inspection included a complete visual inspection of most of the project features. Staff gage readings and existing temporary benchmarks where available were used to determine approximate elevations of water, embankments and weir features. Photographs were taken at each project feature (see Appendix B) and Field Inspection notes were completed in the field to record measurements and deficiencies (see Appendix D).

b. Inspection Results

Closure No. 1

Erosion problems and Hurricane Rita damages were repaired through a maintenance project that was completed in February 2009. The dike was capped and bank paving installed on both ends of the closure. This site is in good condition since this work was performed. (Photos: Appendix A, Photo 1).

Closure No. 2

This structure is in good condition. (Photos: Appendix A, Photo 2)

Closure No. 3

This structure is in good condition. (Photos: Appendix A, Photo 3)





Closure No. 4

This structure is in good condition. (Photos: Appendix A, Photo 4)

Closure No. 5

Water is migrating around the structure on both ends. (Photos: Appendix A, Photos 5 & 6)

Closure No. 6

Water is migrating around the southern end of the structure. (Photos: Appendix A, Photos 7 & 8)

Closure No. 7

This structure is in good condition. (Photos: Appendix A, Photo 9).

Closure No. 8

A maintenance event on the adjacent TV-21 project required the closure to be removed for access. At the conclusion of the TV-21 maintenance event, the contractor replaced the closure and added additional rock to repair the breach. There has been some settlement at the canal opening. (Photos: Appendix A, Photo 10).

Closure No. 9

This rock shoreline feature functions as a breakwater protecting the earthen pipeline closure to the north. The recent construction of the TV-21 East Marsh Island Marsh Creation project has helped to reinforce the breach that had occurred on the southeast corner of the pipeline canal. (Photos: Appendix A, Photo 11)

c. Maintenance Recommendations

i. Immediate/ Emergency Repairs

- A large open water area has developed within the marsh near the western terminus of Closure No. 3 and that the bankline between that point and the eastern end of Closure No. 2 has eroded very severely and such that the "landbridge" between Vermilion Bay on the north of Marsh Island and the northwestern portion of Lake Sand proper is now narrow and may become subject to breaching thus allowing an undesirable water connection between the two bodies of water. NRCS proposed a new rock project to protect the shoreline between closure Nos. 2 & 3. The project was rejected. CPRA and USACE do not plan to pursue the matter further.
- There is a breach on the southern end of the bank paving at Closure No. 5 as well as a section of broken marsh between Closures No. 5 and No. 6, which is allowing exchange to occur between Vermilion Bay and Lake Sand. It is recommended that an additional reach of shoreline protection dike be constructed,





an estimated 1,500 to 1,800 linear feet, to connect the southern end of Closure No. 5 to the northern end of Closure No. 6. NRCS proposed a new rock project to protect the shoreline between closure Nos. 5 & 6. The project was rejected. CPRA and USACE do not plan to pursue the matter further.

ii. Programmatic/ Routine Repairs None

d. Maintenance History

<u>General Maintenance</u>: Below is a summary of completed maintenance projects and operation tasks performed since December 2001, the construction completion date of the Marsh Island Hydrologic Restoration Project (TV-14).

2005 Maintenance Project–Grillot, Inc. (Through lease agreement with Bertucci Contracting Corp.) This maintenance project included the placement of paving stone (18" thick) spread out around the wingwalls of the plug at Lake Sand Canal No. 5 Closure to "harden" the area while still allowing flow in extreme tidal events to pass around the structure without washing away the existing bank. Also included was the extension of the rock dike on the southern end of Canal No. 5. Approximately 4,000 tons of 1000# stone was placed on Lake Sand Closure No. 4 to reconstruct the rock dike where stone was displaced. This maintenance project was a result of damages that occurred during Hurricane Lili in 2002. The costs associated with the engineering, design and construction of the Marsh Island Maintenance Project are as follows:

TOTAL CONSTRUCTION COST:	\$361,413.11
Construction (FEMA) Construction (CWPPRA) E & D, construction oversight, as-builts	\$267,059.11* \$ 64,092.00 \$ 30,262.00

* This cost was reimbursed by FEMA

2008 Repair of Closure No. 8 Breach – This repair work included placing spoil material on the southern end of the rock plug from the dredging of the north-south access canal adjacent to this closure. The work was performed by Renaissance Petroleum Co. as part of their CUP application for a new oil and gas well on the east end of Marsh Island. Additional dredge material was also placed along the entire reach of the west levee of the proposed TV-21 project as well as on the northern end of Closure No. 8 towards the bay connecting to an existing rock dike. Hydraulic dredge material was also pumped behind Structure No. 7 to create marsh behind the rock dike. In addition, spoil material from the bucket dredge operation was placed on the west side of the north-south access canal to bridge a small area of marsh that connects to Structure No. 7. This work was completed in November 2008 and was performed at no cost to CWPPRA and CPRA.



2009 Maintenance Project – Antill Pipeline Construction - This maintenance project included placing 175 tons of 130# rock at Closure No. 1, 370 tons of 130# rock at Closure No. 2, 2,270 tons of 130# rock at Closure No. 4, and 570 tons of 130 # rock at Closure No. 6. Bank paving (using 30# rock) was placed at the ends of all of the closures as part of this project which was completed in February 2009. This maintenance project was a result of damages sustained from Hurricane Rita in 2005 and other required routine maintenance. The costs associated with the engineering, design and construction of the Marsh Island Maintenance Project are as follows:

Project Total	\$515,752.14
E & D, construction oversight, as-builts	\$ 44,627.14
Construction (FEMA) Construction (CWPPRA)	\$113,083.30 \$358,041.70
C_{constant}	¢112.002.20

III. Operation Activity

a. Operation Plan

There are no water control structures associated with this project, therefore no structural operation plan is required.

b. Actual Operations

There are no water control structures associated with this project, therefore no required structural operations.

IV. Monitoring Activity

As mandated in the monitoring plan, the four continuous recorders were removed at the end of 2006. Pursuant to a CWPPRA Task Force decision on August 14, 2003 to adopt the Coastwide Reference Monitoring System-*Wetlands* (CRMS-*Wetlands*) for CWPPRA, updates were made to the TV-14 Monitoring Plan to merge it with CRMS-*Wetlands* and provide more useful information for modeling efforts and future project planning while maintaining the monitoring mandates of the Breaux Act. There are no CRMS-*Wetlands* sites inside the TV-14 project area, however, there are 9 sites located on Marsh Island.

a. Monitoring Goals

The objective of the Marsh Island Hydrologic Restoration Project is to restore more natural hydrologic conditions in the project area resulting in the protection of the existing marsh.





The following goals will contribute to the evaluation of the above objective:

- 1. Reduce water level variability in the project area.
- 2. Decrease the rate of marsh loss in the project area.
- 3. Reduce erosion rate of the northeast shoreline of Marsh Island.
- 4. Increase the occurrence of submerged aquatic vegetation in Lake Sand and in shallow open water within the project area.

b. Monitoring Elements

Aerial Photography:

Near-vertical color-infrared aerial photography (1:12,000 scale) was used to measure vegetated and non-vegetated areas for the project and reference areas. The photography was obtained in 2000 prior to project construction and post-construction in years 2004, 2009 and 2016. The original photography was checked for flight accuracy, color correctness, and clarity and was subsequently archived. Aerial photography was scanned, mosaicked, and georectified by USGS/NWRC personnel according to standard operating procedures (Steyer et al. 1995, revised 2000) (Figure 2).

Percent land trends were calculated using Landsat Thematic Mapper (TM) data for 1985 – 2016. Linear regressions were calculated for the period of record. The variability in percent land data points around the slope illustrate the influence of various sources of environmental variance or classification error. Positive slopes indicate increasing percent land or historical land gain and negative slopes indicate decreasing percent land or historical land loss (Couvillion et al., 2017).








Figure 2. Photomosaic of the 2004 color-infrared aerial photography for the TV-14 project and reference areas from aerial photography taken November 25, 2004.





Shoreline Change:

To document shoreline movement along the northeast shoreline of Marsh Island, a differential GPS (DGPS) survey of unobstructed sections of shoreline was conducted at the vegetative edge of the bank to document the position of the shoreline in pre-construction year 1999 and post-construction in 2003, 2009, 2012 and 2019. A similar survey was conducted concurrently along a 2,000 ft. (609.6 m) section of reference area 2 (R2). DGPS shoreline positions were mapped.

Water Level:

Water level variability was monitored hourly at two continuous data recorders deployed in the project area and two continuous data recorders deployed in reference area 1 (R1) (Figure 3). Staff gauges adjacent to the continuous recorders were surveyed to correlate water levels NAVD88. Hourly water level data were collected at these stations for five years following project construction, from October 1999 to December 2006.

Water level is monitored hourly at station TV21CR02 within the project area and selected reference site CRMS0523, within R1. Water level data were used to document water level variability in the southern part of the TV-14 project area and the reference area.

Submerged Aquatic Vegetation (SAV):

SAV was monitored using the rake method (Chabreck and Hoffpauir 1962). Restoration of the Lake Sand shoreline is expected to influence SAV primarily in Lake Sand, while canal plugs and spoil bank repair work is expected to influence SAV primarily in other shallow open water areas. Separate tests were therefore used to evaluate SAV in Lake Sand and SAV in shallow open water areas. The frequency of occurrence of SAV in Lake Sand was compared to the frequency of occurrence of SAV in Lake Tom found in R1. Three parallel transects were established and separated by a distance approximately equal to one-fourth the pond width (Figure 3). Each transect is composed of a minimum of twenty-five equally spaced sampling stations. At each station, aquatic vegetation was sampled by dragging a garden rake on the pond bottom for one second. The presence of vegetation was recorded to determine the frequency of aquatic plant occurrence (frequency = number of occurrences/ $25 \ge 100$). When vegetation was present, the species present were recorded in order to determine the frequencies of individual species (Nyman and Chabreck 1996). In shallow open water areas, three small ponds in the project area were compared to three small ponds in R1. Two parallel transects, separated by a distance approximately equal to one-third the pond width were established in each pond and investigated using similar sampling techniques as discussed above. Ancillary salinity data, collected with continuous data recorders, will be evaluated in concert with the statistical analysis to aid in the interpretation of SAV data. SAV was monitored in the fall preceding construction in 1999 and in post-construction years 2002, 2004, 2006, 2009, 2012, 2013 and 2016.








Figure 3. Continuous hydrographic monitoring stations and SAV monitoring survey transects for the TV-14 project and reference areas.





IV. Monitoring Activity (continued)

c. Monitoring Results and Discussion

Aerial Photography:

Pre-construction classification (2000) indicated 69.8% land and 30.2% water within the project area and 64.4% land and 35.6% water within R1 (Table 1, Figure 4). Post-construction classification of land area and open water, collected in November 2004, indicated 58.6% land and 41.4% water in the project area and 58.3% land and 41.7% water within R1 (Table 1, Figure 5). However, due to a correction of the project and R1 boundaries resulting in a change in acreage for both areas, the pre- and post-construction classifications are not directly comparable. The project and R1 boundaries were updated to correct inaccuracies due to the low-resolution satellite imagery used to create the boundaries during project planning. Because of the low resolution, some parts of the project and R1 were excluded. For both areas, the boundaries were expanded to include these areas as well as some open water surrounding the project area and R1. As a result, the first comparison of land and water area is being made using the 2009 data. The photography flown on December 20, 2009 indicated 56.3% land and 43.7% water within the project area and 56.2% land and 43.8% water within R1 (Figure 6). These values indicate a loss of approximately 2% land in both the project area and reference areas for the period 2004-2009 (Table 1). The 2016 photography indicated 58.1% land and 41.9% water within the project area compared with 55.5% land and 45.5% water within R1 (Figure 7). This equates to a 1.8% gain in land in the project area since the 2009 analysis compared with a -0.7% loss in the reference area. This is due in large part to the construction of the TV-21 project. Approximately 160 acres of new land were created within the TV-14 project, based on an examination of pre- and post-construction satellite land change data for TV-21 (Couvillion et al. 2017). Removing that from the 2016 land/water analysis results in 55.9% land, demonstrating the project would have had a loss of approximately 0.04% land since 2009 without the marsh creation project.

The general land trend within the project area prior to construction was negative (-0.37%/yr; 27.05 ac/yr) from 1985 to 2001 (Figure 8). Incorporating the 2001 to 2016 data, which includes the post-construction satellite imagery, shows a slightly lower loss trend compared to the preconstruction data (-0.30%/yr; 21.93 ac/yr), demonstrating the overall land change trend of the project area has improved since the construction of the project. Again this is primarily due to the construction of TV-21. If the TV-21 additional acres are excluded as above, the loss rate would be approximately -0.36%/yr, almost identical to the trend prior to construction



Date/Area	% Land	% Water	%Change Land Compared to Prior Analysis
2000 Project	69.8	30.2	N/A
2000 Reference	64.4	35.6	N/A
2004 Project	58.6	41.1	N/A
2004 Reference	58.3	41.7	N/A
2009 Project	56.3	43.7	-2.3
2009 Reference	56.2	43.8	-2.1
2016 Project	58.1	41.9	1.8
2016 Reference	55.5	44.5	-0.7

Table 1. Land and water area percentages and percent change for the project and R1 reference areas 2000-2009.








Figure 4. Results of the 2000 Land:Water GIS image classification for the TV-14 project and reference areas from aerial photography taken November 27, 2000.






Figure 5. Results of the 2004 Land:Water GIS image classification for the TV-14 project and reference areas from aerial photography taken November 25, 2004.








Figure 6. Results of the 2009 Land:Water GIS image classification for the TV-14 project and reference areas from aerial photography taken December 20, 2009.








Figure 7. Results of the 2016 Land: Water GIS image classification for the TV-14 project and reference areas from aerial photography taken October 29, 2016.








Figure 8. Project scale percent land change for TV-14. Percent land values are displayed for all cloud free TM images available from 1985-2016. The blue and red lines depict the pre- and post-construction percent land trends, respectively. Percent land calculated as percent land of total project area. See Couvillion et al. 2017.

Shoreline Position:

Comparison of the 2003 dataset to the preconstruction (1999) data indicated a gain of 1.08 m/yr in the protected section of the shoreline and a loss of -0.62 m/yr in the unprotected section. Comparing the 2009 survey (post-Hurricanes Rita and Ike) to the 2003 survey indicated a loss of -0.77 m/yr in the protected area and -3.58 m/yr in the unprotected area. The post-Hurricane recovery period (comparing 2009-2012) showed a gain of 0.99 m/yr in the protected section while the unprotected section saw a loss of -2.68 m/yr. Comparison of the most recent time period (2012-2019) resulted in a gain of 3.66 m/yr in the protected section and a loss of -5.93 m/yr in the unprotected section. Overall loss from 1999 to 2019 was -4.25 m/yr in the unprotected section, while the protected section showed a gain of 1.22 m/yr (Figure 9).

Time Period	Protected Se	ection	Unprotected S	ection
	Mean Shoreline	SE (+/-)	Mean Shoreline	SE (+/-)
	Change (m/yr)		Change (m/yr)	
1999-2003	1.08	0.54	-0.62	0.59
2003-2009	-0.77	.20	-3.58	0.37
2009-2012	0.99	0.69	-2.68	0.24
2012-2019	3.66	1.14	-5.93	0.47
1999-2019	1.22	0.51	-4.25	0.23








Figure 9. Marsh Island Hydrologic Restoration (TV-14) shoreline change 1999-2019.





Water Level:

Relative water level data for the pre-and post-construction time periods were analyzed from the following datasets:

Station	Data collection period
TV14-01	10/12/1999 - 12/31/2006
TV14-02*	10/12/1999 - 3/14/2002
TV14-23	3/14/2002 - 12/31/2006
TV14-03R	10/12/1999 - 12/31/2006
TV14-04R	10/12/1999 - 12/31/2006
TV21CR02	2/14/2012 - 5/16/19
CRMS0523	2/14/2012 - 5/16/19

*The continuous recorder at TV14-02 was removed because of access problems following project construction. The replacement station, TV14-23 was installed closer to Bayou Blanc, a more accessible location.

The difference in project area and R1 water level range (variability) was significantly higher post-construction than pre-construction (p<0.0001) (R1 had a water level range 0.16' higher than the project area post-construction and 0.06' higher preconstruction). Water level variability in the project area was found to be significantly less than that in R1, for both the pre- and postconstruction periods (Figure 10). Water level variability appeared to increase following project construction in R1 and the project appears to have been successful at preventing a similar increase in the project area. It is not known what factors contributed to the increase in water level variability in R1 following project construction. However, it is not likely to be due to any effects of the project but rather variations in weather and tides. There was less variability in the project area before construction but ranges in the reference area increased relative to the project area post-construction. Thus, the project appears to have reduced water level variability as designed.

Visser (2007) determined that there was a significant decrease in flood stress based on two TV-14 project gauges in an analysis of hydrologic data on CWPPRA Hydrologic Restoration projects. Because the flooding stress was so small in the TV-14 project area, Visser determined that this was not biologically significant. Flooding stress was calculated by multiplying the stress level from flood events of different durations by the percentage of time that the stress level occurred and the percentage of plant productivity.

Water level variability at TV21CR02 was slightly higher than the reference site CRMS0523 during 2012 - 2019, indicating the project has not had an effect on variability within the southern part of the project area. This is not surprising considering the TV-21 recorder is situated within a canal that has open access to West Cote Blanche Bay, unlike the TV-14 recorders that were situated in the northern part of the project area behind the canal closures.

20








Figure 10. Mean daily water level range (variability) \pm standard error during the pre- and postconstruction periods for the project and R1 stations as well as the 2012-2019 monitoring period at stations TV21CR02 and reference recorder CRMS0523.

Submerged Aquatic Vegetation (SAV):

SAV was analyzed separately for large and small ponds (Lake Sand vs. Lake Tom and small ponds in the project area vs. small ponds in R1). An Analysis of Variance (ANOVA) was conducted on frequency of occurrence data for areas (project and reference), years, and interaction between the two. The results showed significantly higher SAV frequency in 2004 and 2016 ($F_{7,125} = 3.4086$, p = 0.0023) than other years (Figure 11). The size of ponds was the most important effect in the model with small ponds having significantly more frequent SAV than larger ones ($F_{1,125} = 6.1451$, p = 0.0145). There was no significant difference in SAV abundance in the project area vs the reference area. The greatest abundance of SAV was in the reference ponds in 1999, 2004, and 2016 where *Myriophyllum spicatum* dominated (Figure 12). Other species were occasionally present including Vallisineria americana in the large project pond in 2006 and *Potamogeton* in the large reference pond in 2009 but none were abundant. *Ceratophyllum demersum* was observed during the 2016 survey but also not in large amounts. The presence or absence of SAV appears to be directly related to variations in climate. Mean annual salinity data for the eastern side of Marsh Island, from project-specific and CRMS continuous recorders, shows a correlation between SAV abundance and annual salinity (Figure 11). Minimal SAV was observed in survey years 2006 - 2013 following the extreme weather events of Hurricanes Rita and Ike as well as the drought in 2011, which increased surface water salinities on the island. A return to normal to above average rainfall in recent years reduced salinities resulting in a significant increase in SAV during the 2016 survey.






Figure 11. Submerged aquatic vegetation abundance calculated separately for small and large ponds and annual salinity for Eastern Marsh Island. Mean \pm SE.








Figure 12. Submerged aquatic vegetation abundance by species for both the project and R1.



V. Conclusions

a. Project Effectiveness

The project has been effective at reducing water level variability within the northern portion of the project area as compared to an ecologically similar reference area (R1). Water level variability did not increase in the project area as it did in R1 post-construction. SAV occurrence increased within the smaller ponds of the project area in 2016, but was virtually absent in the years following Hurricanes Rita and Ike. Climate as well as pond size has had the greatest effect on SAV abundance in the TV-14 project, as SAV decreased in high salinity years and has been virtually absent in Lake Sand through all surveys.

The goal to reduce the erosion rate of the northeast shoreline was partially met. In areas that received protection from a rock dike, erosion rates were much lower than those that were unprotected. The protected areas showed erosion during Hurricanes Rita and Ike, but have been prograding since, particularly on the western side of the project area where a large open water area is filling in. However, as the protected areas showed the highest rates of progradation on the most recent shoreline survey, the unprotected areas showed the highest rates of erosion since project construction.

The goal to decrease the rate of marsh loss in the project area was met due to the construction of the TV-21 East Marsh Island Marsh Creation Project. Land to water analysis showed a slight increase in percent land in the project area from 2009 to 2016, while the reference area R1 showed a slight decrease. The percent land change analysis also showed a reduction in the loss rate for the project area since construction. Without the addition of the TV-21 project, the loss rate would likely be similar to the rate pre-construction.

b. Recommended Improvements

Overall, the Marsh Island Hydrologic Restoration Project is in good condition with most features still functioning as designed after repair. However, as noted above, there are a few areas of concern that if left unattended, could lead to more serious problems occurring. CPRA and the USACE do not intend to pursue maintenance prior to project end of life due to limited funding and the willingness of the CWPPRA program to award further funding to support the proposed maintenance.

c. Lessons Learned

The steel sheet pile, rock riprap wingwalls, and stone bank paving installed at each end of Closure No. 5 after Hurricane Lili proved to be successful in preventing erosion during the Hurricane Rita storm surge event. This application will be applied to other closure sites for bank stabilization and protection.





d. End of Project Life

The construction of the TV-14 structures has effectively reduced water level variability in the northern part of the project area. This reduction in variability combined with the construction of the TV-21 project has reduced the land loss rate in the project area since construction. However, erosion continues unabated on unprotected shoreline reaches. Little remains of the separation between Lake Sand and West Cote Blanche Bay as breaks have formed in the landbridge on the eastern shore of Lake Sand. Without this separation, the project will no longer be effective at reducing variability and without future action will exacerbate future land loss. Therefore, continued upkeep of the project features as well as additional shoreline protection are critical to the long term stability of the project area land mass.





VI. Literature Cited

- Barras, John A. 2006, Land area change in coastal Louisiana after the 2005 hurricanes-a series of three maps: U.S. Geological Survey Open-File Report 06-1274.
- Chabreck, R.H. and C.M. Hoffpauir. 1962. The use of weirs in coastal marsh management in coastal Louisiana. Proceedings of the Annual Conference of the Southeastern Association of Game and Fish Commissioner 16:103-112.
- Chabreck, R.H. and R.G. Linscombe. 1988. Vegetative type map of the Louisiana coastal marshes. Louisiana Wildlife and Fisheries Commission, Baton Rouge, LA.
- Couvillion, B.R., Beck, Holly, Schoolmaster, Donald, and Fischer, Michelle, 2017, Land area change in coastal Louisiana 1932 to 2016: U.S. Geological Survey Scientific Investigations Map 3381, 16 p. pamphlet, <u>https://doi.org/10.3133/sim3381</u>.
- East, J. W., M. J. Turco, and R. R. Mason, Jr. 2008. Monitoring inland storm surge and flooding from Hurricane Ike in Texas and Louisiana. U.S. Geological Survey Open-File Report 2008-1365. 38 pp.
- Hurricane Rita Flood Recovery Maps (Louisiana) [GIS data]. 2006. Washington, D. C.: Federal Emergency Management Agency (FEMA). Available: <u>http://www.fema.gov/hazard/flood/recoverydata/rita/rita_la-gis.shtm</u> [March 30, 2006].
- Louisiana Department of Natural Resources Coastal Restoration and Management Division, Coastal Engineering Division, and Coastal Restoration Division. 2004. 2004 Operations, Maintenance and Monitoring Report for Marsh Island Hydrologic Restoration Project TV-14). Louisiana Department of Natural Resources, Coastal Restoration Division.
- Nyman, J.A. and R.H. Chabreck. 1996. Some effects of 30 years of weir management on coastal marsh aquatic vegetation and implications to waterfowl management. Gulf of Mexico Science 14:16-25.
- Orton, E.W. 1959. A geological study of Marsh Island, Iberia Parish, Louisiana. Tech. Report, Louisiana Wildlife and Fisheries Commission.
- SCS. 1978. Soil survey of Iberia Parish, Louisiana. U.S. Department of Agriculture (USDA), Soil Conservation Service. 67+ pp.
- Steyer, G.D., R.C. Raynie, D.L. Steller, D. Fuller, and E. Swensen. 1995. Quality Management plan for Coastal Wetlands Planning, Protection, and Restoration Act monitoring program. Open-file series no. 95-01. Baton Rouge: Louisiana Department of Natural Resources, Coastal Restoration Division.



- United States Army Corps of Engineers (USACE). 1994. Wetland Value Assessment for Marsh Island Canal Plugging, Shoreline Stabilization and Marsh Restoration (T/V-14). United States Department of the Interior, Army Corps of Engineers. 5pp.
- United States Department of Agriculture, Natural Resources Conservation Service. 2002. The PLANTS Database, Version 3.1 (<u>http://plants.usda.gov)</u>. National Plant Data Center, Baton Rouge, LA 70874-4490 USA. State of Louisiana Plants list downloaded January 14, 2003.
- Visser, J. M., 2007. Analysis of the Hydrologic Data from CWPPRA Hydrologic Restoration Projects, in review. Coastal Ecology Institute of Louisiana State University, Baton Rouge, LA.





APPENDIX A (Inspection Photographs)







Photo No. 1, Closure No. 1



Photo No. 2, Closure No. 2







Photo No. 3, Closure No. 3



Photo No. 4, Closure No. 4

30





Photo No. 5, Closure No. 5, Southern End



Photo No. 6, Closure No. 5, Northern End







Photo No. 7, Closure No. 6



Photo No. 8, Closure No. 6, Southern End







Photo No. 9, Closure No. 7



Photo No. 10, Closure No. 8



33



Photo No. 11, Closure No. 9





APPENDIX B (Three Year Budget Projection)





MARSH ISLAND/ TV-14 / PPL 6 Three-Year Operations & Maintenance Budgets 07/01/2019 - 06/30/2022

Project Manager	<u>O & M Manager</u>	Federal Sponsor	Prepared By
Dion Broussard, P.E.	Dion Broussard, P.E.	COE	Dion Broussard, P.E.
	2019/2020 (-18)	2020/2021 (-19)	2021/2022 (-20)
Maintenance Inspection	\$-	\$ -	\$ -
Structure Operation			
State Administration	\$ 12,432.00	\$ 14,367.00	\$ 16,420.00
Federal Administration	\$-		\$-
Maintenance/Rehabilitation			
14/15 Description:			
E&D	¢		
Construction			
Construction Oversight			
Sub Total - Maint. And Rehab.	-		
15/16 Description :		- -	
13/10 Description .			
E&D	1		
Construction			
Construction Oversight			
	Sub Total - Maint. And Rehab.	\$-	
16/17 Description:			
E&D			\$ -
Construction			¢ _
Construction Oversight			\$ -
Construction Oversight		Sub Total - Maint. And Rehab.	\$ -
		Sub Total - Maint, And Kenab.	Ψ
	2019/2020 (-18)	2020/2021 (-19)	2021/2022 (-20)
Total O&M Budgets	\$ 12,432.00	\$ 14,367.00	\$ 16,420.00
O &M Budget (3 yr Tot			<u>\$ 43,219.00</u>
Unexpended O & M Bu			<u>\$ 200,000.00</u>
Remaining O & M Bud	iget (Projected)		<u>\$ 156,781.00</u>





APPENDIX C (Field Inspection Notes)





				MAINTENA	INSPECTION REPORT CHECK SHEET		
Project No. / Nor	oo:TV 14 March	n Island Hydrologic F	loctoration		Date of Inspection: May 16, 2017 Time: 11:00 AM		
Floject No. / Nar	ne. IV-14 Marsi		estoration		Date of inspection. May 16, 2017 Time. 11.00 AM		
Structure No. 1					Inspector(s): Dion Broussard, Darrell Pontiff, Mark Mouledous (CPRA)		
					Tyson Crouch (LDWF)		
Structure Descrip	tion: Rock Plug	g			Scott Wandell (USACE)		
Type of Inspection	on: Annual				Water Level Inside: Outside:		
	0	Discusional Designation	0	Dista #	Weather Conditions: Clear and Warm Observations and Remarks		
ltem	Condition	Physical Damage	Corrosion	Photo #	Observations and Remarks		
Steel Bulkhead	N/A						
/ Caps							
	N/A						
Stop Logs	N/A						
Hardware	N/A						
Each an Dilan	N1/A						
Timber Piles	N/A						
Timber Wales	N/A						
	IN/A						
Galv. Pile Caps	N/A						
Cables	N/A						
0 0	N/A						
Supports							
Rip Rap (fill)	Good			1	The site is in good condition.		
	Guu			1			
Earthen	N/A						
Embankment							
What are the cor							
Are there any no							
Settlement of roc							
Position of stoplogs at the time of the inspection?							



				MAINTENA	NCE INSPECTION REPORT CHECK SHEET
Project No. / Na	me: IV-14 Marsr	n Island Hydrologic F	Restoration		Date of Inspection: May 16, 2017 Time: 12:15 PM
Structure No. 2					Inspector(s): Dion Broussard, Darrell Pontiff, Mark Mouledous (CPRA)
Official No. 2					Tyson Crouch (LDWF)
Structure Descri	ntion: Rock Plue	n			Scott Wandell (USACE)
		9			
Type of Inspecti	on: Annual				Water Level Inside: Outside:
					Weather Conditions: Clear and Warm
ltem	Condition	Physical Damage	Corrosion	Photo #	Observations and Remarks
Steel Bulkhead	N/A				
/ Caps					
Steel Grating	N/A				
Stop Logs	N/A				
Hardware	N/A				
Timber Piles	N/A				
Timber Wales	N/A				
	N1/A				
Galv. Pile Caps	N/A				
Cables	N/A				
Cables	IN/A				
Signage	N/A				
/Supports					
, ouppoint					
Rip Rap (fill)	Good			2	The site is in good condition.
				_	
Earthen	N/A				
Embankment					
What are the co	nditions of the e	xisting levees?			
Are there any n					
Settlement of roo					
		of the inspection?			
Are there any signs of vandalism?					



2020 Operations, Maintenance, and Monitoring Report for Marsh Island Hydrologic Restoration (TV-14)

Image: Project No. 1990/1000 Image: Project No. 1990/10000 Image: Project No. 1990/1000 <t< th=""><th></th><th></th><th></th><th></th><th></th><th></th></t<>						
Sincurus A. Annald A. Anna					MAINTENA	NCE INSPECTION REPORT CHECK SHEET
Sincurus A. Annald A. Anna	Desired May (May		. Is have all the almost a set of F			
Sincurus periods in Rook Plug and in Physical Danage Corroson Photo # Soft Wadell (USACE) Type of Inspective: Annual Type of Inspective: A	Project No. / Nai	ne: I v-14 Marsr	h Island Hydrologic F	Restoration		Date of Inspection: May 16, 2017 Time: 12:15 PM
Sincurus periods in Rook Plug and in Physical Danage Corroson Photo # Soft Wadell (USACE) Type of Inspective: Annual Type of Inspective: A	Structure No. 3					Inspector(s): Dion Broussard, Darrell Pontiff, Mark Mouledous (CPRA)
Structure Description: Rock Plug Key Big Stock Wandell (USACE) Type of Inspection: Anual Physical Damage Corrosion Photo # Water Lovel wider Condition:						
Image Condition Clear and Watter Conditions: Clear and Watter Observations and Remarks Image Physical Damage Corrow Point Observations and Remarks Steel Builtows NA Image Image Image Steel	Structure Descri	ption: Rock Plug	g			
Image Condition Clear and Watter Conditions: Clear and Watter Observations and Remarks Image Physical Damage Corrow Point Observations and Remarks Steel Builtows NA Image Image Image Steel						
Condition Physical Damage Corrosion Phote # Observations and Remarks Steel Bukhead NA A A A A A Steel Grating NA Image: A intermation of the state of the integration of the state of the integrate of the integration of the state of the integrat	Type of Inspecti	on: Annual				
Shee Buikhed NA Image: Shee Stee Stee Stee Stee Stee Stee Stee						
I canses I canses I canses Steel Grating N/A I canses I canses Steel Lag I canses I canses I canses Steel Lag I canses I canses I canses Steel Lag I canses I canses I canses Hardware N/A I canses I canses N/A I canses I canses I canses Timber Piles N/A I canses I canses Timber Piles N/A I canses I canses Timber Viles N/A I canses I canses Steel Caps N/A I canses I canses Gaix Piles I canses I canses Cables N/A I canses I canses Signage N/A I ca	Item	Condition	Physical Damage	Corrosion	Photo #	Observations and Remarks
I canses I canses I canses Steel Grating N/A I canses I canses Steel Lag I canses I canses I canses Steel Lag I canses I canses I canses Steel Lag I canses I canses I canses Hardware N/A I canses I canses N/A I canses I canses I canses Timber Piles N/A I canses I canses Timber Piles N/A I canses I canses Timber Viles N/A I canses I canses Steel Caps N/A I canses I canses Gaix Piles I canses I canses Cables N/A I canses I canses Signage N/A I ca						
Steel Grating NA Image: Steel Grating NA Image: Steel Grating Stop Logs NA Image: Steel Grating Image: Steel Grating Stop Logs NA Image: Steel Grating Image: Steel Grating Stop Logs NA Image: Steel Grating Image: Steel Grating Stop Logs NA Image: Steel Grating Image: Steel Grating Hardware NA Image: Steel Grating Image: Steel Grating Hardware NA Image: Steel Grating Image: Steel Grating Timber Piles NA Image: Steel Grating Image: Steel Grating Timber Vales NA Image: Steel Grating Image: Steel Grating Galv. Pile Caps NA Image: Steel Grating Image: Steel Grating Galv. Pile Caps NA Image: Steel Grating Image: Steel Grating Galv. Pile Caps NA Image: Steel Grating Image: Steel Grating Steel Grating Image: Steel Grating Image: Steel Grating Image: Steel Grating Steel Grating NA Image: Steel Grating Image: Steel Grating Galv. Pile Caps NA Image: Steel Grating Image: Steel Grating Steel Grating Image: Steel Grating Image: Steel Grating Image: Steel Grating </td <td></td> <td>N/A</td> <td></td> <td></td> <td></td> <td></td>		N/A				
Stop Logs NA Image: Stop Logs NA Image: Stop Logs NA Image: Stop Logs Image: S	/ Caps	N1/A				
And and a second sec	Steel Grating	N/A				
And and a second sec						
And and a second sec	Stop Loge	NI/A				
Image: Angle of the exist o	Ctop Logs	1.07				
Image: Angle of the exist o						
Image: Angle of the exist o	Hardware	N/A				
Imber Wales NA Imber Wales NA Imber Wales <						
Imber Wales NA Imber Wales NA Imber Wales <						
Galv. Pile Caps N/A Image: Caps of the construction of the existing levees? Image: Caps of the construction of stoplogs at the time of the inspection? Image: Caps of the construction of the pinespection?	Timber Piles	N/A				
Galv. Pile Caps N/A Image: Caps of the construction of the existing levees? Image: Caps of the construction of stoplogs at the time of the inspection? Image: Caps of the construction of the pinespection?						
Galv. Pile Caps N/A Image: Caps of the constraints of the existing levees? Image: Caps of the constraints of the existing levees? Image: Caps of the constraints of the existing levees? Galv. Pile Caps N/A Image: Caps of the constraints of the existing levees? Image: Caps of the constraints of the existing levees? Image: Caps of the constraints of the existing levees?						
Cables N/A Image: Cables N/A Image: Cables Image: Cable	Timber Wales	N/A				
Cables N/A Image: Cables N/A Image: Cables Image: Cable						
Signage N/A Image: Constraint of the system of the inspection? Image: Constraint of the system of the inspection? Signage N/A Image: Constraint of the system of the inspection? Image: Constraint of the system of the inspection?	Galv. Pile Caps	N/A				
Signage N/A Image: Constraint of the system of the inspection? Image: Constraint of the system of the inspection? Signage N/A Image: Constraint of the system? Image: Constraint of the system? Signage N/A Image: Constraint of the system? Image: Constraint of the system? Signage N/A Image: Constraint of the system? Image: Constraint of the system? Position of stoplogs at the time of the inspection? Image: Constraint of the system? Image: Constraint of the system?						
Signage N/A Image: Constraint of the system of the inspection? Image: Constraint of the system of the inspection? Signage N/A Image: Constraint of the system? Image: Constraint of the system? Signage N/A Image: Constraint of the system? Image: Constraint of the system? Signage N/A Image: Constraint of the system? Image: Constraint of the system? Position of stoplogs at the time of the inspection? Image: Constraint of the system? Image: Constraint of the system?	Cablaa	NI/A				
/Supports Image: Construction of the existing levees? Image: Construction of the existing levees? What are the conditions of the existing levees? Image: Construction of the existing levees? Image: Construction of the existing levees? Settlement of rock plugs and rock weirs? Image: Construction of the inspection? Image: Construction of the inspection?	Caples	INA				
/Supports Image: Construction of the existing levees? Image: Construction of the existing levees? What are the conditions of the existing levees? Image: Construction of the existing levees? Image: Construction of the existing levees? Settlement of rock plugs and rock weirs? Image: Construction of the inspection? Image: Construction of the inspection?						
/Supports Image: Construction of the existing levees? Image: Construction of the existing levees? What are the conditions of the existing levees? Image: Construction of the existing levees? Image: Construction of the existing levees? Settlement of rock plugs and rock weirs? Image: Construction of the inspection? Image: Construction of the inspection?	Signage	N/A				
Rip Rap (fill) Good Image: Cool of the state of the inspection? Image: Cool of the state of the inspection? Image: Cool of the state of the inspection? Rip Rap (fill) Good Image: Cool of the state of the inspection? Image: Cool of the state of the inspection? Image: Cool of the state of the inspection?						
Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system Image: Constraint of the system I						
Embankment Image: Constraint of the existing levees? What are the conditions of the existing levees? Image: Constraint of the existing levees? Are there any noticeable breaches? Image: Constraint of the exist of	Rip Rap (fill)	Good			3	This site is in good condition.
Embankment Image: Constraint of the existing levees? What are the conditions of the existing levees? Image: Constraint of the existing levees? Are there any noticeable breaches? Image: Constraint of the exist of						
Embankment Image: Constraint of the existing levees? What are the conditions of the existing levees? Image: Constraint of the existing levees? Are there any noticeable breaches? Image: Constraint of the exist of						
What are the conditions of the existing levees? Image: Condition of the existing levees? Are there any noticeable breaches? Image: Condition of the inspection? Settlement of rock plugs and rock weirs? Image: Condition of the inspection?		N/A				
Are there any noticeable breaches? Image: Comparison of the comparison of	Embankment					
Are there any noticeable breaches? Image: Comparison of the comparison of	L	1	ļ		l	
Are there any noticeable breaches? Image: Comparison of the comparison of			viation launa 2			
Settlement of rock plugs and rock weirs? Position of stoplogs at the time of the inspection?						
Position of stoplogs at the time of the inspection?						



2020 Operations, Maintenance, and Monitoring Report for Marsh Island Hydrologic Restoration (TV-14)

				MAINTENA	NCE INSPECTION REPORT CHECK SHEET
Project No. / Nar	ne:TV-14 Mars	h Island Hydrologic F	estoration		Date of Inspection: May 16, 2017 Time: 12:15 PM
Structure No. 4					Inspector(s): Dion Broussard, Darrell Pontiff, Mark Mouledous (CPRA)
					Tyson Crouch (LDWF)
Structure Descrip	otion: Rock Plu	g			Scott Wandell (USACE)
Type of Inspection	on: Annual				Water Level Inside: Outside:
					Weather Conditions: Clear and Warm
ltem	Condition	Physical Damage	Corrosion	Photo #	Observations and Remarks
Steel Bulkhead	N/A				
/ Caps					
Steel Grating	N/A				
Stop Logs	N/A				
etop Logo					
Landerana	N/A				
Hardware	N/A				
Timber Piles	N/A				
Timber Wales	N/A				
Galv. Pile Caps	N/A				
Cables	N/A				
Signage	N/A				
/Supports					
Rip Rap (fill)	Good			4	This site is in good condition.
_ · · ····/					
Earthen	N/A				
Embankment					
What are the cor	nditions of the e	existing levees?			
Are there any no					
Settlement of roc	k plugs and ro	ck weirs?			
		of the inspection?			
	ns of vandalisn				



				MAINTENA	NANCE INSPECTION REPORT CHECK SHEET			
Project No. / Nar	ne:TV-14 Mars	h Island Hydrologic F	Restoration		Date of Inspection: June 19, 2014 Time: 11:15 AM			
Structure No. 5					Inspector(s): Darrell Pontiff, Dion Broussard, Mark Mouledous (CPRA)			
					Tyson Crouch, Cassidy Lejeune (LDWF)			
Structure Descrip	otion: Steel She	eet Pile with Rip Rap			(USACE) Not present			
Tuna of lagranti					Water Level Insider Outsider			
Type of Inspection	on: Annuai				Water Level Inside: Outside: Weather Conditions: Clear and Warm			
Item	Condition	Physical Damage	Corrosion	Photo #	Observations and Remarks			
nem	condition	r nysicar Damage	Corrosion	5	Good			
Steel Bulkhead	Good							
/ Caps								
Steel Grating	N/A							
Stop Logs	N/A							
Hardware	N/A							
Timber Piles	N/A							
Timber Wales	N/A							
Calu Dila Corre	N1/ A							
Galv. Pile Caps	N/A							
Cables	N/A				-			
Cables	IN/A							
Signage	N/A							
/Supports								
Rip Rap (fill)	Good			5&6	Water migrating around structure on both ends.			
/								
Earthen	N/A							
Embankment								
	alitica a stat							
What are the cor Are there any no								
Settlement of roc								
PUSITION OF STODIC	Jus at the time	of the inspection?						



Project No. / Name: TV-14 Mark Island Hydrologic Restoration Date of Inspectors: Nay 16, 2017 Time: 12:00 PM Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Image: Structure No. 6 Structure No. 6 Image: Structure No. 7 Image: Structure No. 6 Image: Structure No. 7 Structure No. 7 Image: Structure No. 7 Image: Structure No. 7 Image: Structure No. 7 Structure No. 7 Image: Structure No. 7 <th></th> <th></th> <th></th> <th></th> <th>MAINTENA</th> <th colspan="3">INSPECTION REPORT CHECK SHEET</th>					MAINTENA	INSPECTION REPORT CHECK SHEET		
Situcture Description: Rock Pluy Type of Inspector(i): Name Condition Physical Damage Corrosin P								
Sucure Deconfusion: Rock Plug South Plane	Project No. / Na	me:TV-14 Marsl	h Island Hydrologic F	Restoration		Date of Inspection: May 16, 2017 Time: 12:00 PM		
Sucure Deconfusion: Rock Plug South Plane								
Structure Description: Rock Plug Soft Wandell (USACE) Tpe of Inspection: Annual Physical Damage Corrosion Photo # Water Level Inside: Outside: Item Condition Physical Damage Corrosion Photo # Observations and Remarks Steel Buikhead NA Image:	Structure No. 6							
Type of Inspection: Annual Water Level Inside: Outside: Outside: Weather Conditions: Clear and Warm Imma Condition Physical Damage Corrosion Phote # Observations and Remarks Steel Bulkhead NA Imma Imma Observations and Remarks Imma Observations and Remarks Steel Graing NA Imma						Tyson Crouch (LDWF)		
Item Condition Physical Damage Corrosion Photo # Observations and Remarks Steel Bukhead N/A Image Image Observations and Remarks Steel Grang N/A Image Image Image Image Steel Grang N/A Image Image Image Image Image Steel Grang N/A Image Image <td>Structure Descri</td> <td>iption: Rock Plu</td> <td>g</td> <td></td> <td></td> <td>Scott Wandell (USACE)</td>	Structure Descri	iption: Rock Plu	g			Scott Wandell (USACE)		
Item Condition Physical Damage Corrosion Photo # Observations and Remarks Steel Bukhead N/A Image Image Observations and Remarks Steel Grang N/A Image Image Image Image Steel Grang N/A Image Image Image Image Image Steel Grang N/A Image Image <td>-</td> <td></td> <td></td> <td></td> <td></td> <td></td>	-							
Item Condition Physical Damage Corrosion Photo # Observations and Remarks Steel Bukhead N/A Image: Steel Graing N/A Image: Steel Graing	Type of Inspect	ion: Annual						
Steel Bulkhead IVA Image: Constraint of the system of			DI D	<u> </u>	DI 4 #			
Image: Capes Image: Capes Image: Capes Image: Capes Steel Graing N/A Image: Capes Image: Capes Stop Logs N/A Image: Capes Image: Capes Stop Logs N/A Image: Capes Image: Capes Hardware N/A Image: Capes Image: Capes Hardware N/A Image: Capes Image: Capes Hardware N/A Image: Capes Image: Capes Timber Piles N/A Image: Capes Image: Capes MA Image: Capes Image: Capes Image: Capes Galv. Pile Caps N/A Image: Capes Image: Capes Galv. Pile Caps N/A Image: Capes Image: Capes N/A Image: Capes Image: Capes Image: Capes Rock Dike Good Image: Capes	Item	Condition	Physical Damage	Corrosion	Photo #	Observations and Remarks		
Image: Capes Image: Capes Image: Capes Image: Capes Steel Graing N/A Image: Capes Image: Capes Stop Logs N/A Image: Capes Image: Capes Stop Logs N/A Image: Capes Image: Capes Hardware N/A Image: Capes Image: Capes Hardware N/A Image: Capes Image: Capes Hardware N/A Image: Capes Image: Capes Timber Piles N/A Image: Capes Image: Capes MA Image: Capes Image: Capes Image: Capes Galv. Pile Caps N/A Image: Capes Image: Capes Galv. Pile Caps N/A Image: Capes Image: Capes N/A Image: Capes Image: Capes Image: Capes Rock Dike Good Image: Capes	Ctool Dullthead	N1/A						
Steel Grating NA Image: Steel Grating NA Image: Steel Grating Stop Logs NA Image: Steel Grating Image: Steel Grating Stop Logs NA Image: Steel Grating Image: Steel Grating Stop Logs NA Image: Steel Grating Image: Steel Grating Stop Logs NA Image: Steel Grating Image: Steel Grating Ardware NA Image: Steel Grating Image: Steel Grating Ardware NA Image: Steel Grating Image: Steel Grating Timber Piles NA Image: Steel Grating Image: Steel Grating Timber Vales NA Image: Steel Grating Image: Steel Grating Galv. Pile Caps NA Image: Steel Grating Image: Steel Grating Galv. Pile Caps NA Image: Steel Grating Image: Steel Grating Galv. Pile Caps NA Image: Steel Grating Image: Steel Grating Signage NA Image: Steel Grating Image: Steel Grating Signage NA Image: Steel Grating Image: Steel Grating Kock Dike Good Image: Steel Grating Image: Steel Grating What are the conditions of the existing leves? Image: Steel Grating Image: Steel Grating Are there any noti	-	IN/A						
Stop Logs N/A		NI/A						
Hardware NA Image: Second	Steel Grating	IN/A						
Hardware NA Image: Second								
Hardware NA Image: Second	Stop Logs	N/A						
Timber Piles N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales Timber Wales Image: Construction of the existing levees? Timber Wales Timber Wales Image: Construction of the existing levees? Timber Wales Timber Wales Timber Wales What are the conditions of the existing levees? Timber Wales Settlement of rock plugs and rock weins? Timber Wales Position of stopologs at the time of the inspection? Timber Wales	Otop Logs	1.07.1						
Timber Piles N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales Timber Wales Image: Construction of the existing levees? Timber Wales Timber Wales Image: Construction of the existing levees? Timber Wales Timber Wales Timber Wales What are the conditions of the existing levees? Timber Wales Settlement of rock plugs and rock weins? Timber Wales Position of stopologs at the time of the inspection? Timber Wales								
Timber Piles N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales N/A Image: Construction of the existing levees? Timber Wales Timber Wales Image: Construction of the existing levees? Timber Wales Timber Wales Image: Construction of the existing levees? Timber Wales Timber Wales Timber Wales What are the conditions of the existing levees? Timber Wales Settlement of rock plugs and rock weins? Timber Wales Position of stopologs at the time of the inspection? Timber Wales	Hardware	N/A						
Timber Wales N/A Image: Construction of the existing levees? Galv. Pile Caps N/A Image: Construction of the existing levees? Galv. Pile Caps N/A Image: Construction of the existing levees? Galv. Pile Caps N/A Image: Construction of the existing levees? Galv. Pile Caps N/A Image: Construction of the existing levees? Galv. Pile Caps Image: Construction of the existing levees? Image: Construction of the existing levees? Settlement of cock plugs and rock weirs? Image: Construction of the inspection? Image: Construction of the inspection?	i la avaio	1071						
Timber Wales N/A Image: Construction of the existing levees? Galv. Pile Caps N/A Image: Construction of the existing levees? Galv. Pile Caps N/A Image: Construction of the existing levees? Galv. Pile Caps N/A Image: Construction of the existing levees? Galv. Pile Caps N/A Image: Construction of the existing levees? Galv. Pile Caps Image: Construction of the existing levees? Image: Construction of the existing levees? Settlement of cock plugs and rock weirs? Image: Construction of the inspection? Image: Construction of the inspection?								
Timber Wales N/A Image: Construction of the existing levees? Galv. Pile Caps N/A Image: Construction of the existing levees? Galv. Pile Caps N/A Image: Construction of the existing levees? Galv. Pile Caps N/A Image: Construction of the existing levees? Galv. Pile Caps N/A Image: Construction of the existing levees? Galv. Pile Caps Image: Construction of the existing levees? Image: Construction of the existing levees? Settlement of cock plugs and rock weirs? Image: Construction of the inspection? Image: Construction of the inspection?	Timber Piles	N/A						
Galv. Pile Caps N/A Image: Capse of the system of the maps of the								
Galv. Pile Caps N/A Image: Capse of the system of the maps of the								
Cables N/A Image: Cables of the existing levees? Image: Cables of the existing levees? Signage N/A Image: Cables of the existing levees? Image: Cables of the existing levees? What are the conditions of the existing levees? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of rock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees?	Timber Wales	N/A						
Cables N/A Image: Cables of the existing levees? Image: Cables of the existing levees? Signage N/A Image: Cables of the existing levees? Image: Cables of the existing levees? What are the conditions of the existing levees? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of rock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees?								
Cables N/A Image: Cables of the existing levees? Image: Cables of the existing levees? Signage N/A Image: Cables of the existing levees? Image: Cables of the existing levees? What are the conditions of the existing levees? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of rock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees? Settlement of strock plugs and rock weirs? Image: Cables of the existing levees? Image: Cables of the existing levees?	Galv. Pile Caps	N/A						
Signage N/A Image: Constraint of the section?	· · · · ·							
Signage N/A Image: Constraint of the section?								
/Supports	Cables	N/A						
/Supports								
/Supports								
Rock Dike Good 7 & 8 Water migrating around southern end of structure. Earthen N/A Image: Construct of the conditions of the existing levees? Image: Construct of the conditions of the existing levees? What are the conditions of the existing levees? Image: Construct of the conditions of the existing levees? Image: Construct of the conditions of the existing levees? Settlement of rock plugs and rock weirs? Image: Construct of the conditions? Image: Construct of the conditions?		N/A						
Earthen N/A Embankment Image: Constraint of the sector of the existing levees? What are the conditions of the existing levees? Image: Constraint of the existing levees? What are there any noticeable breaches? Image: Constraint of the existing levees? Settlement of rock plugs and rock weirs? Image: Constraint of the existing levees? Position of stoplogs at the time of the inspection? Image: Constraint of the existing levees?	/Supports							
Earthen N/A Embankment Image: Constraint of the sector of the existing levees? What are the conditions of the existing levees? Are there any noticeable breaches? Settlement of rock plugs and rock weirs? Position of stoplogs at the time of the inspection?								
Embankment	Rock Dike	Good			7 & 8	Water migrating around southern end of structure.		
Embankment								
Embankment	F (1							
What are the conditions of the existing levees? Image: Condition of the existing levees? Are there any noticeable breaches? Image: Condition of the exist level of the exi		N/A						
Are there any noticeable breaches? Settlement of rock plugs and rock weirs? Position of stoplogs at the time of the inspection?	Embankment							
Are there any noticeable breaches? Settlement of rock plugs and rock weirs? Position of stoplogs at the time of the inspection?								
Are there any noticeable breaches? Settlement of rock plugs and rock weirs? Position of stoplogs at the time of the inspection?	What are the as	nditions of the a	visting lovpos2					
Settlement of rock plugs and rock weirs? Position of stoplogs at the time of the inspection?								
Position of stoplogs at the time of the inspection?								
	, the there any SI	g or variationsh						





				MAINTENA	NCE INSPECTION REPORT CHECK SHEET
Project No. / Na	me:TV-14 Marsh	n Island Hydrologic F	Restoration		Date of Inspection: May 16, 2017 Time: 11:45 AM
Structure No. 7					Inspector(s): Dion Broussard, Darrell Pontiff, Mark Mouledous (CPRA)
Official No. 7					Tyson Crouch (LDWF)
Structure Descri	ption: Rock Dike	Э			Scott Wandell (USACE)
Type of Inspect	ion: Annual				Water Level Inside: Outside:
					Weather Conditions: Clear and Warm
Item	Condition	Physical Damage	Corrosion	Photo #	Observations and Remarks
Ote et Duillete et	N1/A				
Steel Bulkhead	N/A				
/ Caps Steel Grating	N/A				
Steel Grating	IN/A				
Stop Logs	N/A				
Hardware	N/A				
Timber Piles	N/A				
Timber Wales	N/A				
	N1/A				
Galv. Pile Caps	N/A				
Cables	N/A				
Cablob					
Signage	N/A				
/Supports					
Rock Dike	Good			9	The site is in good condition.
Earthen	N/A				
Embankment					
What are the co	nditions of the e	xisting levees?			
Are there any n					
Settlement of ro					
		of the inspection?			
Are there any si					






			1	MAINTENA	NCE INSPECTION REPORT CHECK SHEET
Project No. / Nar	me:TV-14 Marsl	n Island Hydrologic R	estoration		Date of Inspection: May 16, 2017 Time: 11:45 AM
Structure No. 8					Inspector(s): Dion Broussard, Darrell Pontiff, Mark Mouledous (CPRA)
					Tyson Crouch (LDWF)
Structure Descrip	otion: Rock Plu	g			Scott Wandell (USACE)
Type of Inspection	on: Annual				Water Level Inside: Outside:
.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,					Weather Conditions: Clear and Warm
ltem	Condition	Physical Damage	Corrosion	Photo #	Observations and Remarks
Steel Bulkhead	NI/A				
/ Caps					
	N/A				
otoor orating					
Stop Logs	N/A				
0.00 2090					
Hardware	N/A				
aiuwaie					
Timber Piles	N/A				
Timber Plies	N/A				
Taskan Malaa	N1/A				
Timber Wales	N/A				
Galv. Pile Caps	N/A				
Cables	N/A				
Signage	N/A				
/Supports					
Rock Plug	Good			10	Breach on southern end of closure was repaired in conjunction with TV-21 maintenance event.
					Some settlement of canal plug.
Earthen	N/A				
Embankment					
What are the cor	ditions of the e	xisting levees?			
Are there any no					
Settlement of roo					
		of the inspection?			
	ins of vandalism				





				MAINTENA	NCE INSPECTION REPORT CHECK SHEET
Project No. / Na	me:TV-14 Marsh	n Island Hydrologic F	Restoration		Date of Inspection: May 16, 2017 Time: 11:00 AM
Structure No. 9					Inspector(s): Dion Broussard, Darrell Pontiff, Mark Mouledous (CPRA)
Structure No. 9					Tyson Crouch (LDWF)
Structure Descri	intion: Rock Plue	7			Scott Wandell (USACE)
Type of Inspect	ion: Annual				Water Level Inside: Outside:
					Weather Conditions: Clear and Warm
ltem	Condition	Physical Damage	Corrosion	Photo #	Observations and Remarks
Steel Bulkhead	N/A				
/ Caps					
Steel Grating	N/A				
Stop Logs	N/A				
Hardware	N/A				
Timber Piles	N/A				
Timber Plies	IN/A				
Timber Wales	N/A				
Galv. Pile Caps	N/A				
Cables	N/A				
Signage	N/A				
/Supports					
Rock Dike	Fair			11	Dike is settling in some areas. Breach is closed and shoreline looks good since the TV-21 project.
F and a set	N1/A				
Earthen Embankment	N/A				
Embankment					
What are the co	nditions of the o	visting lavees?			
Are there any n					
Settlement of ro					
		of the inspection?			
Are there any si	ans of vandalism	1?			







TV-14 Marsh Island Hydrologic Restoration

Project Completion Date December 2001





